



SJWAA Baseball Fields

11500 125th St.

Largo, FL 33774

6/29/21

Professional Fertilizer & Landscaping

210 S Hillcrest Ave.

Clearwater, FL 33756 (727)

657-8675

gabejsmith76@gmail.com



Field #1 Baseball Field

All infield area to be excavated 4 inches and taken to an off site location for dump. A sand/soil mix will be installed for drainage below the Celebration Bermuda.

Infield area will be installed with Celebration Bermuda.

A separate zone with 6 - 10 sprinkler heads will be installed. Complete with sprinkler wire, high pressure valve and schedule 40 pipe. Infield area will be trenched to proper depth for irrigation lines.

All clay areas of infield skin will be reversed tilled. Preparation for laser grade. Entire infield will be laser graded to acceptable levels for proper drainage.

Pitcher mound and home plate will have TURFACE Mound Clay added to areas for better drainage and play.

All bases, home plate and pitching rubber will be removed and reset to proper distances.

Sod and clay will be rolled with a commercial 2 ton roller.

Clean up to pre-renovation.

Total Cost Field 1 - \$12,800.00



Field #2 Baseball Field

All infield area where grass is going will be excavated 4 inches in depth.

Excavation material will be hauled off to an off site location for dump. A sand/soil mix will be installed below grass for proper drainage.

Celebration bermuda will be installed to complete infield area.

A separate irrigation zone containing 6 -12 sprinkler heads will be installed complete with irrigation wire and schedule 40 pipe. Trenching will be done to proper depth to set irrigation pipe. Zone comes complete with its separate high pressure valve.

Infield clay area will be reversed tilled for preparation of laser grade.

Entire infield area will be set to proper height and slope for proper drainage by laser grade.

TURFACE Mound Clay will be used on pitcher mound and home plate areas to insure better drainage.

All sod and clay will be rolled with a 2 ton commercial roller.

All bases, pitcher mound and home plate will be removed then reset to proper distances.

Clean up to pre-renovation.

Total Cost Field #2 - \$19,600



Field #4 Baseball Field

Entire infield area to be cut, removed and raised to proper level by laser grade.

Entire clay infield area will be laser graded to correct slope for proper drainage.

All bases, home plate and pitching rubber will be removed then reset when grade is complete to correct distances.

TURFACE Mound Clay will be used on home plate and pitcher mound areas to aid in drainage and for better play.

All clay areas will be rolled with a commercial 2 ton roller.

Clean up to pre-renovation.

Total Cost Field #4 - \$5,600.00

Any questions pertaining to estimate, please call Gabe Smith at (727) 657-8675.