QUOTE #1 RECOMMENDED



ESTIMATE

Efrain Figueroa

1015 Omaha Cir Palm Harbor, FL, 34683-4036 US Date created: 2025-04-16 12:27 PM

Date sent to the customer: 2025-04-03 03:11 PM

License #: CCC1331484





QUOTE #2













ROOF REPLACEMENT PROPOSAL

We can help you with Roofing, Gutters and Repairs Residential and Commercial

Office: (813) 560-2998

KAT COHAN

1015 Omaha Circle Palm Harbor, FL 34683 kcohan@neighborly.org 7277541100

SCOPE OF WORK

Description	Qty	Unit price	Line total
Main Building Flat Roofing Sections			
1. Pull permits for roofing with city and meet with city for all necessary inspections.			
2. Take actions to cover any shrubs, windows, grass etc. with tarps to protect from roofing debris debris. Place plywood over any A/C's and other equipment as needed.			
3. Sweep excess granules off existing roofing material and dispose of using roll off dumpsters in front parking lot (wood blocks placed to prevent pavement scratching)			
4. Remove old lead pipe flashings and remove roofing around drains.			
5. Install 1" polyiso insulation to entire roof surface.			
6. Install new 3" by 3" drip edge flashing (color: white) on entire roof perimeter.			
7. Install 60 Mil energy saving TPO roofing system over entire flat roof area. TPO will be adhered using olybond adhesive, seams will be hot air welded with robotic heat welder.			
8. 2 A/C's must be lifted onto proper four prong stands per florida building code by licensed A/C contractor	2	\$800.00	\$1,600.00
9. 2 A/C dog house covers must be removed inorder to install TPO under, then put back in place by licensed A/C contractor	2	\$1,000.00	\$2,000.00
10. Install new TPO flashings around all pipes and vents.			
11. Wrap around all AC's with TPO material.			
12. Quality control check entire project, probe all TPO welds and ensure water proof bond is achieved.			
Total Price:	শ্	\$45,342.00	\$45,342.00
		Quote subtotal	\$48,942.00
		Total	\$48,942.00

10 Year Trust Roofing Labor Warrantee 20 Year TPO material Warrantee

Payments will be paid as followed: 1/2 upon material delivery, 1/2 upon completion of job.

Timeline: Work will take approximately 3-5 working days



Signature X

12016 South Road • Hudson, Florida 34669

Pasco 727-844-8549

Pinellas 727-777-8740 Hillsborough 813-424-1541

Date of Acceptance X

 $www. Bay To Bay Roo fing.com \bullet Bay To Bay Roo fing @Gmail.com$

State Certified Roofing Contractor License # CCC1330112

QUOTE #3

THE ROOFING PROFESSIONALS RESIDENTIAL • COMMERCIAL

	BONDED & INSURED • FREE ESTIMATES		
PROPOSAL SUBMITTED TO Neighborly Senior Care Network	PHONE 813-407-2995 DATE 04/07/2025		
STREET 1015 Omaha Circle	LOCATION		
CITY, STATE AND ZIP Palm Harbor, FL 34683	Sales Rep - Scott Julian 727-534-8763		
PLATINUM 25YR WORKMANSHIP WARRANTY SHINGLE			
Option 1 STYLE Owens Corning Duration COLOR TBD MANUFACTURER'S WARRANTY 50yr Shingle PRICE \$52,588.00 WE HEREBY SUBMIT SPECIFICATIONS AND ESTIMATES FOR: Option 1 Option 2 CHECK ALL THAT APPLY Obtain and Post Local Roof Permits (in accordance with local law Call in all inspections required by municipality. Call in all inspections required by municipality. Completely Remove Existing Roof to Bare Wood. Thoroughly Inspect Roof Decking. Repair Rotten Decking at \$85.00 per sheet plywood and/or \$8.50 L.F. of decking and all other woodwork. 1x2 and 1x3 will be billed at half the above price. Specialty Wood TBD at \$TBD L.F. Re-nail entire roof decking per Florida building code with proper fasteners. Re-nail entire roof decking peel & stick over entire roof deck per Florida Building Code. Install New Drip Edge. Natural • White • Brown • Grey • Black • Be Install New lining in Valleys and Sealed with Asphalt Roof Cem	and Nailed and Sealed with Asphalt Roof Cement. Double Seal All Flashings with Asphalt Roof Cement. Install N/A Off Ridge Vents (Hip Roofs). Install Premium Shingle Over Vent for Attic Ventilation. N/AL.F. Install N/A L.F. Standard Aluminum Ridge Vent Clean and Haul away all job related debris to an approved disposal facility. Clean out Gutters. Provide a continuous clean up of job site while job is in progress. Hand clean and magnetically sweep job site for nails.		
Option 1 STYLE Modified Bitumin COLOR White MANUFACTURER'S WARRANTY 10 yr PRICE Included in price Option 1 Option 2 CHECK ALL THAT APPLY Obtain and Post Local Roof Permits (in accordance with local law) Call in all inspections required by municipality. Remove Existing Mod Roof to Bare Wood. Go over existing roof. Thoroughly inspect roof decking. Replace Rotten Decking at \$85.00 per sheet plywood and/or \$ 8.50 L.F. of decking and all other woodwork. 1x2 and 1x3 will be billed at half of above price per L.F. Specialty Wood N/A at \$N/A L.F. Re-Nail entire roof decking per Florida Building Code with proper fasteners. Install a new Drip Edge. Natural • White • Brown • Gray • Black • Be \$500.00 courtesy wood credit included at no cost. Wind Mitigation Report included.	Florida Building Code Install a modified roof system, Granulated Make proper tie-in to sloped roof. Clean and haul away all job related debris to an approved disposal facility. Hand clean and magnetically sweep job site for nails. Install Thermoplastic Polyolefin (TPO) N/A We recommend a tapered roof system for the elevation of		
\$600.00 Home Magazine discount coupon applied to price. Owens Corning Platinum Warranty for shingle portion of roof. Any flashing, counter flashing, stucco, and any wood needed, to be determined by field supervisor during re-roof installation. Gutters to remain. Bay To Bay Roofing to assist with disconnecting and re installing (4) HVAC units as needed during install, and included in pricing. HVAC stands included in pricing as needed per Florida hurricane code.			
WE PROPOSE hereby to furnish material and labor - complete in accorpayment schedule set forth below, unless job is not completed. Debit/Credi If Included, wind mitigation to be performed after final payment is received. Payment to be made as follows: Balance due upon substantial completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing, 90% due upon completion of work 10% deposit due upon signing upon completion of work 10% deposit due upon signing upon completion of work 10% deposit due upon signing upon completion of work 10% deposit due upon signing upon completion of work 10% deposit due upon completion of work 10%	it Card fees will apply.(Removal of additional layer of roof will be \$25 per square) Dollars (\$52,588.00) but		
be subject to a service charge of 1.5% per month beginning	Authorized Signature X Scott Julian NOTE: This proposal may be withdrawn by us if not accepted within 30 days.		
Acceptance of Proposal - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above I HAVE READ AND AGREE TO THE TERMS AND CONDITIONS ON REVERSE SIDE, SAID TERMS BEING PART OF THIS CONTRACT.			