

## GOODS AND SERVICES AGREEMENT

**THIS GOODS AND SERVICES AGREEMENT** (“Agreement”) is made as of this \_\_\_\_ day of \_\_\_\_\_, 201\_\_\_\_ (“Effective Date”), by and between Pinellas County, a political subdivision of the State of Florida (“County”), and Oshkosh Airport Products, LLC (“Contractor”) (individually, “Party,” collectively, “Parties”).

### WITNESSETH:

**WHEREAS**, the County requested proposals pursuant to 22-0236-B(DG)Airport Rescue Fire Fighting Truck; and

**WHEREAS**, based upon the County's assessment of Contractor's proposal, the County selected the Contractor to provide the Services as defined herein; and

**WHEREAS**, Contractor represents that it has the experience and expertise to perform the Services as set forth in this Agreement.

**NOW, THEREFORE**, in consideration of the above recitals, the mutual covenants, agreements, terms and conditions herein, and other good and valuable consideration, the receipt and sufficiency of which is hereby mutually acknowledged, the Parties agree as follows:

#### 1. Definitions.

**A. “Agreement”** means this Agreement, including all Exhibits, which are expressly incorporated herein by reference, and any amendments thereto.

**B. “County Confidential Information”** means any County information deemed confidential and/or exempt from Section 119.07, Florida Statutes, and Section 24(a), Article 1 of the Florida Constitution, or other applicable law and any other information designated in writing by the County as County Confidential Information.

**C. “Contractor Confidential Information”** means any Contractor information that is designated as confidential and/or exempt by Florida’s public records law, including information that constitutes a trade secret pursuant to Chapter 688, Florida Statutes, and is designated in this Agreement or in writing as a trade secret by Contractor (unless otherwise determined to be a public record by applicable Florida law). Notwithstanding the foregoing, Contractor Confidential Information does not include information that: (i) becomes public other than as a result of a disclosure by the County in breach of the Agreement; (ii) becomes available to the County on a non-confidential basis from a source other than Contractor, which is not prohibited from disclosing such information by obligation to Contractor; (iii) is known by the County prior to its receipt from Contractor without any obligation or confidentiality with respect thereto; or (iv) is developed by the County independently of any disclosures made by Contractor.

**D. “Contractor Personnel”** means all employees of Contractor, and all employees of subcontractors of Contractor, including, but not limited to temporary and/or leased employees, who are providing the Services at any time during the project term.

**E. “Services”** means the work, duties and obligations to be carried out and performed safely by Contractor under this Agreement, as described throughout this Agreement and as specifically described in Exhibit A (“Statement of Work”) attached hereto and incorporated herein by reference. As used in this Agreement, Services shall include any component task, subtask, service, or function inherent, necessary, or a customary part of the Services, but not specifically described in this Agreement, and shall include the provision of all standard day-to-day administrative, overhead, and internal expenses, including costs of bonds and insurance as required herein, labor, materials, equipment, safety equipment, products, office supplies, consumables, tools, postage, computer hardware/software, telephone charges, copier usage, fax charges, travel, lodging, and per diem and all other costs required to perform Services except as otherwise specifically provided in this Agreement.

2. The execution of this Agreement is subject to and expressly limited by the Terms and Conditions hereon. County and the Contractor are not bound by additional provisions or provisions at variance herewith that may appear in the Contractor's quotation, acknowledgement in force, or any other communication from Contractor to or from County unless such provision is expressly set forth herein.

3. **Services.**

**A. Services.** The County retains Contractor, and Contractor agrees to provide the Services. All Services shall be performed to the satisfaction of the County, and shall be subject to the provisions and terms contained herein and the Exhibits attached hereto.

**B. Services Requiring Prior Approval.** Contractor shall not commence work on any Services requiring prior written authorization in the Statement of Work without approval from the Airport Operations Manager or County designee.

**C. Additional Services.** From the Effective Date and for the duration of the project, the County may elect to have Contractor perform Services that are not specifically described in the Statement of Work attached hereto but are related to the Services ("Additional Services"), in which event Contractor shall perform such Additional Services for the compensation specified in the Statement of Work attached hereto. Contractor shall commence performing the applicable Additional Services promptly upon receipt of written approval as provided herein.

**D. De-scoping of Services.** The County reserves the right, in its sole discretion, to de-scope Services upon written notification to the Contractor by the County. Upon issuance and receipt of the notification, the Contractor and the County shall enter into a written amendment reducing the appropriate Services Fee for the impacted Services by a sum equal to the amount associated with the de-scoped Services as defined in the payment schedule in this Agreement, if applicable, or as determined by mutual written consent of both Parties based upon the scope of work performed prior to issuance of notification.

**E. Independent Contractor Status and Compliance with the Immigration Reform and Control Act.** Contractor is and shall remain an independent contractor and is neither agent, employee, partner, nor joint venturer of County. Contractor acknowledges that it is responsible for complying with the provisions of the Immigration Reform and Control Act of 1986 located at 8 U.S.C. 1324, et seq, and regulations relating thereto, as either may be amended from time to time. Failure to comply with the above provisions shall be considered a material breach of the Agreement.

**F. Non-Exclusive Services.** This is a non-exclusive Agreement. During the term of this Agreement, and any extensions thereof, the County reserves the right to contract for another provider for similar services as it determines necessary in its sole discretion.

**G. Project Monitoring.** During the term of the Agreement, Contractor shall cooperate with the County, either directly or through its representatives, in monitoring Contractor's progress and performance of this Agreement.

4. **Term of Agreement.**

**A. Initial Term.** The term of this Agreement shall commence on the Effective Date and shall remain in full force through delivery and final acceptance by the County or until termination of the Agreement, whichever occurs first. The Contractor will deliver the goods, in the ordered quantities set out in Exhibit C, on or before April 31st, 2023. In the event, Contractor fails to deliver the goods in full by the Delivery Date, in addition to all other legal remedies available to the County, the County reserves the right to immediately terminate the Agreement without penalty to County.

**5. Survivability.** Costs associated with purchases using the authority provided by this contract will survive the contract itself operating under the contract terms and conditions. The duration of purchase orders for recurring deliveries of commodities or performance of services shall not exceed the expiration of the cooperative term contract by more than twelve (12) months. Invoices may be billed for these costs on an “in arrears” basis for an additional twelve (12) month period beyond the contract expiration.

**6. Orders.** Within the term of this Agreement, County may place one or more orders for goods and services at the prices listed on the Price Schedule which is attached hereto as Exhibit C and which is incorporated by reference hereto.

**7. Delivery / Claims.** Prices on the Schedule of Prices are F.O.B. Destination, FREIGHT INCLUDED and unloaded to location(s) within Pinellas County. Actual delivery address(es) will be identified at time of order. Contractor will be responsible for making any and all claims against carriers for missing or damaged items.

**8. Inspection.** In County’s sole discretion, goods rejected due to inferior quality or workmanship will be returned to Contractor at Contractor’s expense and are not to be replaced except upon receipt of written instructions from County.

**9. Material Quality.** - All goods and materials purchased and delivered pursuant to this Agreement will be of first quality and not damaged and/or factory seconds. Any materials damaged or not in first quality condition upon receipt must be exchanged within twenty-four (24) hours of notice to the Contractor at no charge to County.

**10. Material Safety Data.** In accordance with OSHA Hazardous Communications Standards, it is the Contractor seller's duty to advise if a product is a toxic substance and to provide a Material Safety Data Sheet at time of delivery.

**11. Purchase Order Number.** Each order will contain the Purchase Order Number applicable to this Agreement, and such Purchase Order Number must appear on all packing slips, invoices and all correspondence relating to the Order. County will not be responsible for goods delivered without a Purchase Order Number.

**12. Variation in Quantity.** County assumes no liability for goods or materials produced, processed or shipped in excess of the amounts ordered pursuant to the terms of this Agreement.

**13. Warranty.** Seller warrants that the goods are of first quality and as described in Prices Schedule. All manufacturer, producer or seller warranties offered to any other purchaser are expressly available and applicable to County.

#### **14. Compensation and Method of Payment.**

**A. Goods and Services Fee.** As total compensation for the Services, the County shall pay the Contractor the sums as provided in this Section 14 (“Goods and Services Fee”), pursuant to the terms and conditions as provided in this Agreement. It is acknowledged and agreed by Contractor that this compensation constitutes a limitation upon County's obligation to compensate Contractor for such Services required by this Agreement but does not constitute a limitation upon Contractor's obligation to perform all of the Services required by this Agreement. In no event will the Services Fee paid exceed the not-to-exceed sums set out in subsections 14 B. and C., unless the Parties agree to increase this sum by written amendment as authorized in Section 37 of the Agreement.

**B.** The County agrees to pay the Contractor the annual not-to-exceed lump sum of \$783,255.00, for the Airport Rescue Fire Fighting Truck as provided herein as Exhibit A, Scope of work, inclusive of vehicle, warranty, ancillary equipment and any associated delivery costs, payable in accordance with the fixed- fee provided in Exhibit C, payable upon submittal of invoice as required herein.

#### **C. Travel Expenses.**

The Services Fee includes all travel, lodging and per diem expenses incurred by Contractor in performing the Services.

**D. Taxes.** Contractor acknowledges that the County is not subject to any state or federal sales, use, transportation and certain excise taxes.

**Payments and Invoicing.** Contractor shall submit invoices for payments due as provided herein and authorized reimbursable expenses incurred with such documentation as required by County. Invoices shall be submitted as provided in Exhibit D attached hereto.

For time and materials Services, all Contractor Personnel shall maintain logs of time worked, and each invoice shall state the date and number of hours worked for Services authorized to be billed on a time and materials basis. All payments shall be made in accordance with the requirements of Section 218.70 et seq., Florida Statutes, “The Local Government Prompt Payment Act.” The County may dispute any payments invoiced by Contractor in accordance with the County’s Invoice Payments Dispute Resolution Process established in accordance with Section 218.76, Florida Statutes, and any such disputes shall be resolved in accordance with the County’s Dispute Resolution Process.

**15. Acceptance of Goods Services.** For all Services deliverables that require County acceptance as provided in the Statement of Work, the County, through the Department Director of Humans Services or County designee, will have ten (10) calendar days to review the deliverable(s) after receipt or completion of same by Contractor, and either accept or reject the deliverable(s) by written notice to Oshkosh Airport Products, LLC. If a deliverable is rejected, the written notice from the County will specify any required changes, deficiencies, and/or additions necessary. Contractor shall then have seven (7) calendar days to revise the deliverable(s) to resubmit and/or complete the deliverable(s) for review and approval by the County, who will then have seven (7) calendar days to review and approve, or reject the deliverable(s); provided however, that Contractor shall not be responsible for any delays in the overall project schedule that result from the County’s failure to timely approve or reject deliverable(s) as provided herein. Upon final acceptance of the deliverable(s), the County will accept the deliverable(s) in writing.

**16. Discounts.** Delay in receiving an invoice, invoicing for materials shipped ahead of specified schedule, or invoices rendered with errors or omissions will be considered just cause for County to withhold payment without losing discount privileges. Discount privilege will apply from date of scheduled delivery, the date or receipt of goods, or the date of approved invoice, whichever is later.

## 17. Subcontracting/Assignment.

**A. Subcontracting.** Contractor is fully responsible for completion of the Services required by this Agreement and for completion of all subcontractor work, if authorized as provided herein. Contractor shall not subcontract any work under this Agreement to any subcontractor other than the subcontractors specified in the proposal and previously approved by the County, without the prior written consent of the County, which shall be determined by the County in its sole discretion.

**B. Assignment.** This Agreement, and all rights or obligations hereunder, shall not be assigned, transferred, or delegated in whole or in part, including by acquisition of assets, merger, consolidation, dissolution, operation of law, change in effective control of the Contractor, or any other assignment, transfer, or delegation of rights or obligations, without the prior written consent of the County. The Contractor shall provide written notice to the County within fifteen (15) calendar days of any action or occurrence assigning the Agreement or any rights or obligations hereunder as described in this section. In the event the County does not consent to the assignment, as determined in its sole discretion, the purported assignment in violation of this section shall be null and void, and the County may elect to terminate this Agreement by providing written notice of its election to terminate pursuant to this provision upon fifteen (15) days notice to Contractor.

## 18. Personnel.

**A. E-Verify.** The Contractor and Subcontractor must register with and use the E-verify system in accordance with Florida Statute 448.095. The County will verify the work authorization of the Contractor and Subcontractor. A Contractor and Subcontractor may not enter into a contract with the County unless each party registers with and uses the E-verify system.

If a Contractor enters a contract with a Subcontractor, the Subcontractor must provide the Contractor with an affidavit stating that the Subcontractor does not employ, contract with, or subcontract with unauthorized aliens. The Contractor must maintain a copy of the affidavit for the duration of the contract.

If the County, Contractor, or Subcontractor has a good faith belief that a person or entity with which it is contracting has knowingly violated Florida Statute 448.09(1) shall immediately terminate the contract with the person or entity.

If the County has a good faith belief that a Subcontractor knowingly violated this provision, but the Contractor otherwise complied with this provision, the County will notify the Contractor and order that the Contractor immediately terminate the contract with the Subcontractor.

A contract terminated under the provisions of this section is not a breach of contract and may not be considered as such. Any contract termination under the provisions of this section may be challenged to Section 448.095(2)(d), Florida Statute. Contractor acknowledges upon termination of this agreement by the County for violation of this section by Contractor, Contractor may not be awarded a public contract for at least one (1) year. Contractor acknowledges that Contractor is liable for any additional costs incurred by the County as a result of termination of any contract for a violation of this section.

Contractor or Subcontractor shall insert in any subcontracts the clauses set forth in this section, requiring the subcontracts to include these clauses in any lower tier subcontracts. Contractor shall be responsible for compliance by any Subcontractor or Lower Tier Subcontractor with the clause set for in this section.

**B. Qualified Personnel.** Contractor agrees that each person performing Services in connection with this Agreement shall have the qualifications and shall fulfill the requirements set forth in this Agreement.

**19. Name Changes.** The Contractor is responsible for immediately notifying the County of any company name change, which would cause invoicing to change from the name used at the time of the original Agreement.

**20. Compliance with Laws.** Contractor shall comply with all applicable federal, state, county and local laws, ordinances, rules and regulations in the performance of its obligations under this Agreement, including the procurement of permits and certificates where required, and including but not limited to laws related to Workers Compensation, Americans with Disabilities Act (ADA), Section 504 of the Rehabilitation Act of 1973, Minority Business Enterprise (MBE), occupational safety and health and the environment, equal employment opportunity, privacy of medical records and information, as applicable. Failure to comply with any of the above provisions shall be considered a material breach of the Agreement.

**21. Applicable Law and Venue.** This Agreement and any and all purchases made hereunder shall be governed by and construed in accordance with the laws of the State of Florida (without regard to principles of conflicts of laws). The Parties agree that all actions or proceedings arising in connection with this Agreement shall be tried and litigated exclusively in the state or federal (if permitted by law and a Party elects to file an action in federal court) courts located in or for Pinellas County, Florida. This choice of venue is intended by the Parties to be mandatory and not permissive in nature, and to preclude the possibility of litigation between the Parties with respect to, or arising out of, this Agreement in any jurisdiction other than that specified in this section. Each Party waives any right it may have to assert the doctrine of *forum non conveniens* or similar doctrine or to object to venue with respect to any proceeding brought in accordance with this section.

**22. Public Entities Crimes**

Contractor is directed to the Florida Public Entities Crime Act, Section 287.133, Florida Statutes, as well as Florida Statute 287.135 regarding Scrutinized Companies, and represents to County that Contractor is qualified to transact business with public entities in Florida, and to enter into and fully perform this Agreement subject to the provisions state therein. Failure to comply with any of the above provisions shall be considered a material breach of the Agreement.

**23. Waiver.** No waiver by either Party of any breach or violation of any covenant, term, condition, or provision of this Agreement or of the provisions of any ordinance or law, shall be construed to waive any other term, covenant, condition, provisions, ordinance or law, or of any subsequent breach or violation of the same.

**24. Due Authority.** Each Party to this Agreement represents and warrants that: (i) it has the full right and authority and has obtained all necessary approvals to enter into this Agreement; (ii) each person executing this Agreement on behalf of the Party is authorized to do so; (iii) this Agreement constitutes a valid and legally binding obligation of the Party, enforceable in accordance with its terms.

**25. Remedies.** County and Contractor will have all remedies afforded by applicable law.

**26. Termination.** County reserves the right to terminate this agreement, without cause by giving thirty (30) days prior written notice to the Contractor of the intention to terminate or with cause if at any time the Contractor fails to fulfill or abide by any of the terms or conditions specified. Failure of the Contractor to comply with any of the provisions of this Agreement is considered a material breach of Agreement and is cause for immediate termination of the Agreement at the sole discretion of County.

In addition to all other legal remedies available to the County, the County reserves the right to terminate and obtain from another source any services which have not been provided within the period of time stated in the proposal, or if no such time is stated, within a reasonable period of time from the date of request, as determined by the County.

**27. Time is of the Essence.** Time is of the essence with respect to all provisions of this Agreement that specify a time for performance, including the Services as described in Exhibits attached hereto; provided, however, that the foregoing shall not be construed to limit a Party's cure period allowed in the Agreement.

## **28. Confidential Information and Public Records.**

**A. County Confidential Information.** Contractor shall not disclose to any third party County Confidential Information that Contractor, through its Contractor Personnel, has access to or has received from the County pursuant to its performance of Services pursuant to the Agreement, unless approved in writing by the County Contract Manager. All such County Confidential Information will be held in trust and confidence from the date of disclosure by the County, and discussions involving such County Confidential Information shall be limited to Contractor Personnel as is necessary to complete the Services.

**B. Contractor Confidential Information.** All Contractor Confidential Information received by the County from Contractor will be held in trust and confidence from the date of disclosure by Contractor and discussions involving such Contractor Confidential Information shall be limited to the members of the County's staff and the County's subcontractors who require such information in the performance of this Agreement. The County acknowledges and agrees to respect the copyrights, registrations, trade secrets and other proprietary rights of Contractor in the Contractor Confidential Information during and after the term of the Agreement and shall at all times maintain the confidentiality of the Contractor Confidential Information provided to the County, subject to federal law and the laws of the State of Florida related to public records disclosure. Contractor shall be solely responsible for taking any and all action it deems necessary to protect its Contractor Confidential Information except as provided herein. Contractor acknowledges that the County is subject to public records legislation, including but not limited to Chapter 119, Florida Statutes, and the Florida Rules of Judicial Administration, and that any of the County's obligations under this Section may be superseded by its obligations under any requirements of said laws.

**C. Public Records.** Contractor acknowledges that information and data it manages as part of the services may be public records in accordance with Chapter 119, Florida Statutes and Pinellas County public records policies. Contractor agrees that prior to providing services it will implement policies and procedures to maintain, produce, secure, and retain public records in accordance with applicable laws, regulations, and County policies, including but not limited to the Section 119.0701, Florida Statutes. Notwithstanding any other provision of this Agreement relating to compensation, the Contractor agrees to charge the County, and/or any third parties requesting public records only such fees allowed by Section 119.07, Florida Statutes, and County policy for locating and producing public records during the term of this Agreement.

**If the Contractor has questions regarding the application of Chapter 119, Florida Statutes, to the Contractor's duty to provide public records relating to this contract, contact the Pinellas County Board of County Commissioners, Purchasing and Risk Management Department, Operations Manager custodian of public records at 727-464-3311, [purchase@pinellascounty.org](mailto:purchase@pinellascounty.org), Pinellas County Government, Purchasing and Risk Management Department, Operations Manager, 400 S. Ft. Harrison Ave, 6<sup>th</sup> Floor, Clearwater, FL 33756.**

**29. Audit.** Contractor shall retain all records relating to this Agreement for a period of at least five (5) years after final payment is made. All records shall be kept in such a way as will permit their inspection pursuant to Chapter 119, Florida Statutes. In addition, County reserves the right to examine and/or audit such records.

### **30. Digital Accessibility**

Supplier acknowledges and warrants that all digital content and services provided under this contract conforms and shall continue to conform during the Term of this Agreement to the W3C Web Content Accessibility Guidelines, version 2.0 ("WCAG 2.0") at conformance Level A and AA. If all digital content and services does not fully conform to WCAG 2.0 A and AA, Supplier shall advise Pinellas County in writing of the nonconformance prior to execution of this Agreement and shall provide Pinellas County a plan to achieve conformance to WCAG 2.0 A and AA, including but not limited to, an intended timeline for conformance. Failure to achieve conformance, as determined in Pinellas County's sole discretion, on its intended timeline shall be considered a material breach of this Agreement and grounds for termination by Pinellas County.

If during the Term of this Agreement, Supplier fails to maintain compliance with WCAG 2.0 A and AA or Pinellas County otherwise identifies an issue related to accessibility of the product (the "Accessibility Issue") that renders the product inaccessible, then Pinellas County shall notify Supplier of non-compliance. Within 30 days of

Supplier's receipt of a non-compliance notice ("Notice"), Supplier and Pinellas County shall meet and mutually agree upon an appropriate timeline for resolution of the Accessibility Issue(s) ("Initial Meeting").

Should Supplier:

- i. fail to acknowledge receipt of the notice within 30 days of receipt of the Notice;
- ii. unreasonably and solely withhold agreement regarding a timeline for resolution for more than 30 days following the Initial Meeting; or
- iii. fail to materially resolve the Accessibility Issue(s) within the agreed-upon timeline,

Failure to comply with the requirements of this section shall constitute a material breach of this Agreement and shall be grounds for termination of this Agreement by Pinellas County and subject Supplier to section 30 of this Agreement, "Indemnification."

### **31. Liability and Insurance.**

- A. **Insurance.** Contractor shall comply with the insurance requirements set out in Exhibit B, attached hereto and incorporated herein by reference.
- B. **Indemnification.** Contractor agrees to indemnify, pay the cost of defense, including attorney's fees, and hold harmless the County, its officers, employees and agents from all damages, suits, actions or claims, including reasonable attorney's fees incurred by the County, of any character brought on account of any injuries or damages received or sustained by any person, persons, or property, or in any way relating to or arising from the Agreement; or on account of any act or omission, neglect or misconduct of Contractor; or by, or on account of, any claim or amounts recovered under the Workers' Compensation Law; or of any other laws, regulations, ordinance, order or decree; or arising from or by reason of any actual or claimed trademark, patent or copyright infringement or litigation based thereon; or for any violation of requirements of the Americans with Disabilities Act of 1990, as may be amended, and all rules and regulations issued pursuant thereto (collectively the "ADA") except when such injury, damage, or violation was caused by the sole negligence of the County.
- C. **Liability.** Neither the County nor Contractor shall make any express or implied agreements, guaranties or representations, or incur any debt, in the name of or on behalf of the other Party. Neither the County nor Contractor shall be obligated by or have any liability under any agreements or representations made by the other that are not expressly authorized hereunder. The County shall have no liability or obligation for any damages to any person or property directly or indirectly arising out of the operation by Contractor of its business, whether caused by Contractor's negligence or willful action or failure to act.
- D. **Contractor's Taxes.** The County will have no liability for any sales, service, value added, use, excise, gross receipts, property, workers' compensation, unemployment compensation, withholding or other taxes, whether levied upon Contractor or Contractor's assets, or upon the County in connection with Services performed or business conducted by Contractor. Payment of all such taxes and liabilities shall be the responsibility of Contractor.

**32. County's Funding.** The Agreement is not a general obligation of the County. It is understood that neither this Agreement nor any representation by any County employee or officer creates any obligation to appropriate or make monies available for the purpose of the Agreement beyond the fiscal year in which this Agreement is executed. No liability shall be incurred by the County, or any department, beyond the monies budgeted and available for this purpose. If funds are not appropriated by the County for any or all of this Agreement, the County shall not be obligated to pay any sums provided pursuant to this Agreement beyond the portion for which funds are appropriated. The County agrees to promptly notify Contractor in writing of such failure of appropriation, and upon receipt of such notice, this Agreement, and all rights and obligations contained herein, shall terminate without liability or penalty to the County.

**33. Survival.** Any provisions in which by their nature would survive the expiration or termination of the Term of this Agreement.

**34. Notices.** All notices, authorizations, and requests in connection with this Agreement shall be deemed given on the day they are: (1) deposited in the U.S. mail, postage prepaid, certified or registered, return receipt requested; or (2) sent by air express courier (e.g., Federal Express, Airborne, etc.), charges prepaid, return receipt requested; or (iii) sent via email and addressed as set forth below, which designated person(s) may be amended by either Party by giving written notice to the other Party:

For County:

Attn: Erin Johnson  
 Airport Operations Manager  
 Pinellas County Human Services  
 14700 Terminal Blvd,  
 Clearwater, FL 33762

For Contractor:

Oshkosh Airport Products, LLC  
 1515 County Road O, Suite A  
 Neenah, WI 54956

Attn: Dustin Raddatz  
 920-215-5127  
 draddatz@airport.oshkoshcorp.com

with a copy to:  
 Purchasing Director  
 Pinellas County Purchasing Department  
 400 South Fort Harrison Avenue  
 Clearwater, FL 33756

**35. Conflict of Interest.**

- A. The Contractor represents that it presently has no interest and shall acquire no interest, either direct or indirect, which would conflict in any manner with the performance of the Services required hereunder, and that no person having any such interest shall be employed by Contractor during the agreement term and any extensions.
- B. The Contractor shall promptly notify the County in writing of any business association, interest, or other circumstance which constitutes a conflict of interest as provided herein. If the Contractor is in doubt as to whether a prospective business association, interest, or other circumstance constitutes a conflict of interest, the Contract may identify the prospective business association, interest or circumstance, the nature of work that the Contractor may undertake and request an opinion as to whether the business association, interest or circumstance constitutes a conflict of interest if entered into by the Contractor. The County agrees to notify the Contractor of its opinion within (10) calendar days of receipt of notification by the Contractor, which shall be binding on the Contractor.

**36. Right to Ownership.** All work created, originated and/or prepared by Contractor in performing Services pursuant to the Agreement, including any reports, diagrams, materials lists and other documentation or improvements related thereto, to the extent that such work, products, documentation, materials or information are described in or required by the Services (collectively, the "Work Product") shall be County's property when completed and accepted, if acceptance is required in this Agreement, and the County has made payment of the sums due therefore. The ideas, concepts, know-how or techniques developed during the course of this Agreement by the Contractor or jointly by Contractor and the County may be used by the County without obligation of notice or accounting to the Contractor. Any data, information or other materials furnished by the County for use by Contractor under this Agreement shall remain the sole property of the County.

**37. Amendment.** This Agreement may be amended by mutual written agreement of the Parties hereto.

**38. Severability.** The terms and conditions of this Agreement shall be deemed to be severable. Consequently, if any clause, term, or condition hereof shall be held to be illegal or void, such determination shall not affect the validity or legality of the remaining terms and conditions, and notwithstanding any such determination, this Agreement shall

continue in full force and effect unless the particular clause, term, or condition held to be illegal or void renders the balance of the Agreement impossible to perform.

**39. No Third Party Beneficiary.** The Parties hereto acknowledge and agree that there are no third party beneficiaries to this Agreement. Persons or entities not a party to this Agreement may not claim any benefit from this Agreement or as third party beneficiaries hereto.

**40. Entirety.** This Agreement constitutes the entire Agreement between the Parties and supersedes all prior negotiations, representations or agreements either oral or written.

**41. Force Majeure.** “Force Majeure Event” means any act or event that (i) prevents a Party (the “Nonperforming Party”) from performing its obligations or satisfying a condition to the other Party’s (the “Performing Party”) obligations under this Agreement, (ii) is beyond the reasonable control of and not the fault of the Nonperforming Party, and (iii) the Nonperforming Party has not, through commercially reasonable efforts, been able to avoid or overcome. Force Majeure Event(s) do not include economic hardship, changes in market conditions or insufficiency of funds. If a Force Majeure Event occurs, the Nonperforming Party is excused from the performance thereby prevented and from satisfying any conditions precedent to the Performing Party’s performance that cannot be satisfied, in each case to the extent limited or prevented by the Force Majeure Event. The Nonperforming Party must promptly notify the Performing Party upon the occurrence of a Force Majeure Event. When the Nonperforming Party is able to resume its performance or satisfy the conditions precedent to the Performing Party’s obligations, the Nonperforming Party will resume performance under this Agreement without undue delay. Each Party will use commercially reasonable efforts to mitigate the effect of a Force Majeure Event

*(Signature Page Follows)*

IN WITNESS WHEREOF, the Parties hereto have executed this Agreement the day and year first written.

PINELLAS COUNTY, FLORIDA

By and through its

Board of County Commissioners

Oshkosh Airport Products, LLC.

By

By:

*George M Alvarez*

Signature

George M. Alvarez

Print Name

Director - Finance

Title

ATTEST:

Ken Burke,  
Clerk of the Circuit Court

By:

Deputy Clerk

Approved as to Form

**APPROVED AS TO FORM**

By: Keiah Townsend  
Office of the County Attorney

By:

Office of the County Attorney

# EXHIBIT A

## SCOPE OF WORK

### AIRCRAFT RESCUE AND FIRE FIGHTING (ARFF) VEHICLE

1. SCOPE. This Procurement Specification (PS) covers a commercially produced diesel engine driven ARFF vehicle for an [redacted] airport. It includes a 1500 gallon water/Aqueous Film Forming Foam (AFFF) fire suppression system:

The ARFF vehicle is intended to carry rescue and fire fighting equipment for the purpose of rescuing aircraft passengers, preventing aircraft fire loss, and combating fires in aircraft.

2. CLASSIFICATION. The ARFF vehicle(s) covered by this PS are classified in accordance with Part 139, Certification and Operations: Land Airports Serving Certain Air Carriers, Section 315, Aircraft Rescue and Firefighting: Index Determination; Section 317, Aircraft Rescue and Firefighting: Equipment and Agents; and Federal Aviation Administration (FAA) Advisory Circular (AC) 150/5220-10, Guide Specification for Aircraft Rescue and Fire Fighting (ARFF) Vehicles, as follows:

Airport Index	Vehicle Class	Minimum Rated Capacities (gallons/liters)
	4	1500 gallon (5678 liter) water/AFFF solution

3. VEHICLE CONFORMANCE/PERFORMANCE CHARACTERISTICS. The ARFF vehicle will be in accordance with the applicable requirements of National Fire Protection Association (NFPA) 414, Standard for Aircraft Rescue and Fire Fighting Vehicles (2007 Edition), and AC 150/5220-10, Guide Specification for Aircraft Rescue and Fire Fighting (ARFF) Vehicles.

#### 3.1 General Administration Requirements.

3.1.1 Manuals: Technical manuals will consist of operator, service, and parts manuals. All manuals are required to be provided in hardcopy and in digital format on CDs when requested.

3.1.1.1 Technical manuals. The overall format for the manuals will be commercial. Each technical manual will have a title page. Line art will be used to the maximum extent possible for illustrations and parts lists. One complete set of engine and transmission parts, service and operator's manuals will be packed with each vehicle.

- a. The contractor will provide digitized manuals in CD format when requested in addition to or in place of printed paper copies.
- b. The contractor will provide two complete sets of hardcopy manuals and / or CDs when requested.

3.1.1.1.1 Operator's manual. The operator's manual will include all information required for the safe and efficient operation of the vehicle, including fire extinguishing systems, equipment, and any special attachments or auxiliary support equipment. As a minimum, the operator's manual will include the following:

- a. The location and function of all controls and instruments will be illustrated and functionally described.
- b. Safety information that is consistent with the safety standards established by the Occupational Safety and Health Administration (OSHA) and NFPA.
- c. All operational and inspection checks and adjustments in preparation for placing the vehicle into service upon receipt from the manufacturer.
- d. Tie down procedures for transport on a low-boy trailer.
- e. Warranty information and the period of the warranty coverage for the complete vehicle and for any component warranty that exceeds the warranty of the complete vehicle. Addresses and telephone numbers will be provided for all warranty providers.
- f. General description and necessary step-by-step instructions for the operation of the vehicle and its fire extinguishing system(s) and auxiliary equipment.
- g. A description of the post-operational procedures (draining, flushing, re-servicing, et cetera).
- h. Daily maintenance inspection checklists that the operator is expected to perform, including basic troubleshooting procedures.
- i. Disabled vehicle towing procedures.
- j. Procedures and equipment required for changing a tire.
- k. Schedules (hours, miles, time periods) for required preventative maintenance and required periodic maintenance.
- l. Line art drawing of the vehicle, including panoramic views (front, rear, left, and right sides) showing basic dimensions and weights (total vehicle and individual axle weight for the unloaded and fully loaded vehicle). For the purposes of this AC, "unloaded" is defined as a lack of agent, occupants and compartment load, and "loaded" is defined as including agent, occupants and compartment load.

3.1.1.1.2 Service manual. The service manual will identify all special tools and test equipment required to perform servicing, inspection, and testing. The manual will cover troubleshooting and maintenance as well as minor and major repair procedures. The text will contain performance specifications, tolerances, and fluid capacities; current, voltage, and resistance data; test procedures; and illustrations and exploded views as may be required to

permit proper maintenance by qualified vehicle mechanics. The manual will contain an alphabetical subject index as well as a table of contents. The service manual will contain at least the following, where applicable:

- a. Fire fighting system schematic(s).
- b. Hydraulic schematic.
- c. Pneumatic schematic.
- d. Electrical schematic.
- e. Winterization schematic.
- f. Fuel schematic.
- g. Schedules for required preventative maintenance and required periodic maintenance.
- h. Lubrication locations, procedures, and intervals for parts of the vehicle and equipment that require lubrication.

3.1.1.1.3 Parts identification manual. The parts manual will include illustrations or exploded views (as needed) to identify properly all parts, assemblies, subassemblies, and special equipment. All components of assemblies shown in illustrations or exploded views will be identified by reference numbers that correspond to the reference numbers in the parts lists. All purchased parts will be cross-referenced with the original equipment manufacturer's (OEM) name and part number. The parts identification manual will provide the description and quantity of each item used for each vehicle. The size, thread dimensions, torque specifications, and special characteristics will be provided for all nonstandard nuts, bolts, screws, washers, grease fittings, and similar items. The manual will contain a numerical index. The parts manual will contain a list of all of the component vendor names, addresses, and telephone numbers referenced in the parts list.

### 3.1.2 Painting, plating, and corrosion control.

3.1.2.1 Finish. Exterior surfaces will be prepared, primed, and painted in accordance with all of the paint manufacturer's instructions and recommendations. Vehicles will be painted and marked in accordance with AC 150/5210-5, Painting, Marking, and Lighting of Vehicles Used on an Airport. The interior finish of all compartments will be based on the manufacturer's standard production practice. This may include painting, texturing, coating or machine swirling as determined by the manufacturer. All bright metal and anodized parts, such as mirrors, horns, light bezels, tread plates, and roll-up compartment doors, will not be painted. All other surfaces capable of being painted must be in the appropriate yellow-green color.

3.1.2.2 Dissimilar metals. Dissimilar metals, as defined in MIL-STD-889, Dissimilar Metals, will not be in contact with each other. Metal plating or metal spraying of dissimilar base metals to provide electromotively compatible abutting surfaces is acceptable. The use of

dissimilar metals separated by suitable insulating material is permitted, except in systems where bridging of insulation materials by an electrically conductive fluid can occur.

3.1.2.3 Protection against deterioration. Materials that deteriorate when exposed to sunlight, weather, or operational conditions normally encountered during service will not be used or will have a means of protection against such deterioration that does not prevent compliance with performance requirements. Protective coatings that chip, crack, or scale with age or extremes of climatic conditions or when exposed to heat will not be used.

3.1.2.4 Reflective stripes. A minimum eight (8) inch horizontal band of high gloss white paint or white reflective tape (Retroreflective, ASTM-D 4956-09, *Standard Specification for Retroreflective Sheeting for Traffic Control*, TYPE III & above) must be applied around the vehicle's surface.

3.1.2.5 Lettering. The manufacturer will apply the airport's 'Name' and 'Insignia' (if available) in a contrasting color or by decal on both sides of the vehicle in long radius elliptical arches above and below the lettering center line. The size of the lettering will be a minimum of 2½-inches to a maximum of 6-inches. Reflective lettering is allowed if the material is the same as that which is used for the reflective stripe (as specified in AC 150/5210-5).

3.1.3 Vehicle identification plate. A permanently marked identification plate will be securely mounted at the driver's compartment. The identification plate will contain the following information:

- a. NOMENCLATURE
- b. MANUFACTURER'S MAKE AND MODEL
- c. MANUFACTURER'S SERIAL NUMBER
- d. VEHICLE CURB WEIGHT: kg (pounds)
- e. PAYLOAD, MAXIMUM: kg (pounds)
- f. GROSS VEHICLE WEIGHT (GVW): kg (pounds)
- g. FUEL CAPACITY AND TYPE: gals (gallons)
- h. DATE OF DELIVERY (month and year)
- i. WARRANTY (months and km (miles))
- j. CONTRACT NUMBER
- k. PAINT COLOR AND NUMBER

A second permanently marked information data plate will be securely mounted on the interior of the driver's compartment. The plate will contain the information required by NFPA 414, Standard for Aircraft Rescue and Fire Fighting Vehicles (2007 Edition), Section 1.3.5 Vehicle

Information Data Plate. A single plate that combines or contains the information required for both plates is acceptable.

#### 3.1.4 Environmental conditions.

3.1.4.1 Vehicle operation and storage temperature conditions will vary with geographical location. Thus, the locality temperature range can go from  $-40^{\circ}$  to  $110^{\circ}\text{F}$ . Refer to NFPA 414 for vehicle winterization criteria.



3.1.5 Reduction of potential foreign object damage. All loose metal parts, such as pins, will be securely attached to the vehicle with wire ropes or chains. Removable exterior access panels, if provided, will be attached with captive fasteners.

#### 3.1.6 Vehicle Mobility.

3.1.6.1 Operating terrain. The vehicle will be capable of operating safely on paved roads, graded gravel roads, cross country terrain, and sandy soil environments. Cross country terrain consists of open fields, broken ground, and uneven terrain. An off-road, high-mobility suspension system resulting in no more than  $0.5 G_{\text{rms}}$  acceleration at the driver's seat of the vehicle when traversing an 8-inch (20 cm) diameter half round at 35 mph (56 kph) must be provided. The suspension design by which the manufacturer meets the suspension performance requirements is at the manufacturer's discretion.

3.1.6.2 Gradeability. The fully loaded vehicle will be able to ascend any paved slope up to and including 50-percent.

3.1.6.3 Side slope stability. The fully loaded vehicle will be stable on a  $30^{\circ}$  side slope when tested in accordance with NFPA 414.

3.1.6.4 Cornering stability. The fully loaded vehicle will be stable in accordance with NFPA 414 when tested in accordance with NFPA 414.

### 3.2 Weights and dimensions.

3.2.1 Overall dimensions. The maximum dimensions listed below are desirable to ensure vehicles can be accommodated in existing fire stations. Likewise, the overall dimensions should be held to a minimum that is consistent with the best operational performance of the vehicle and the design concepts needed to achieve this performance and to provide maximum maneuverability in accordance with NFPA 414.

<b>Vehicle Capacity /Dimensions</b>	<b>1500 Gallon</b>
Length (inches/cm)	433/1100
Width (inches/cm, excluding mirrors)	124/315
Height (inches/cm)	154/391

**NOTE:** *For Airport Operator Validation: Consult AC 150/5210-15, Aircraft Rescue and Fire Fighting Station Building Design, Appendix A, to ensure vehicles measurements do not exceed existing airport fire station dimensions.*

<b>VEHICLE MEASUREMENT VALIDATION</b>
<b>ADO/FAA Approval:</b> → _____

3.2.2 Angles of approach and departure. The fully loaded vehicle will have angles of approach and departure of not less than 30°.

3.2.3 Field of vision. The vehicle will have a field of vision in accordance with NFPA 414.

3.2.3.1 Mirrors. Combination flat and convex outside rearview mirrors will be installed on each side of the cab. The flat mirrors will be of the motorized remote control type, providing not less than 60° horizontal rotational viewing range. The flat mirrors will also have electrically heated heads. Mirror remote and heating controls will be located on the instrument panel within reach of the seated driver. To provide the driver a clear view of the area ahead of the vehicle and to eliminate potential blind spots, a rectangular mirror will be installed on the lower corner of each side of the windshield, having a minimum area of 35 square inches.

### 3.3 Chassis and vehicle components.

3.3.1 Engine. The vehicle will have a turbocharged diesel engine that is certified to comply with the Environmental Protection Agency (EPA) and state laws for off-highway emission requirements at the time of manufacture. The engine and transmission must operate efficiently and without detrimental effect to any drive train components when lubricated with standard, commercially available lubricants according to the recommendations of the engine and transmission manufacturers.

3.3.1.1 Acceleration. The fully loaded vehicle will accelerate from 0 to 50 miles per hour (mph) on a level paved road within: 25 seconds.

3.3.1.2 Maximum speed. The fully loaded vehicle will attain a minimum top speed of 70 mph on a level, paved road.

3.3.1.3 Pump and roll on a 40-percent grade. The fully loaded vehicle will be capable of pump and roll operations on a paved, dry, 40-percent grade in accordance with NFPA 414.

3.3.1.4 Altitude. Where justified, the vehicle, including the pumping system, will be designed for operation at 2,000 feet above sea level.

#### **JUSTIFICATION**

**ADO/FAA Approval:** ⇨ \_\_\_\_\_

3.3.2 Engine cooling system. The engine cooling system will be in accordance with NFPA 414. A label will be installed near the engine coolant reservoir reading “Engine Coolant Fill.”

3.3.3 Fuel system. The fuel system will be in accordance with NFPA 414.

3.3.3.1 Fuel priming pump. The vehicle will be equipped with an electric or pneumatic fuel pump in addition to the mechanical fuel pump. The electric/pneumatic pump will be used as a priming pump capable of re-priming the engines fuel system.

3.3.3.2 Fuel tank. The vehicle will have one or two fuel tanks with a minimum usable capacity in accordance with NFPA 414, as amended by NFPA 414. Each tank will have a fill opening of 3 inches minimum, readily accessible to personnel standing on the ground and designed to prevent fuel splash while refueling. Each tank will be located and mounted so as to provide maximum protection from damage, exhaust heat, and ground fires. If more than one tank is furnished, means will be provided to assure equalized fuel level in both tanks. An

overturn fuel valve will be provided for each tank to prevent spillage in the event of a rollover. Each fuel tank must be prominently labeled “Diesel Fuel Only”.

3.3.4 Exhaust system. The exhaust system will be in accordance with NFPA 414. The exhaust system will be constructed of high grade rust resistant materials and protected from damage resulting from travel over rough terrain. The muffler(s) will be constructed of aluminized steel or stainless steel. Exhaust system outlet(s) will be directed upward or to the rear, away from personnel accessing equipment compartments and the engine air intake, and will not be directed toward the ground.

3.3.5 Transmission. A fully automatic transmission will be provided. The transmission will be in accordance with NFPA 414.

3.3.6 Driveline. The vehicle driveline will be in accordance with NFPA 414. If the driveline is equipped with a differential locking control, a warning/caution label will be placed in view of the driver indicating the proper differential locking/un-locking procedures. The operator’s manual will also include a similar warning/caution. All moving parts requiring routine lubrication must have a means of providing for such lubrication. There must be no pressure lubrication fittings where their normal use would damage grease seals or other parts.

3.3.7 Axle capacity. Each axle will have a rated capacity, as established by the axle manufacturer, in accordance with NFPA 414.

3.3.8 Suspension. The suspension system will be in accordance with NFPA 414 and AC 150/5220-10, Guide Specification for Aircraft Rescue and Fire Fighting (ARFF) Vehicles.

3.3.9 Tires and wheels. Tires and wheels will be in accordance with NFPA 414. The vehicle will be equipped with single tires and wheels at all wheel positions. The vehicle will be equipped with tubeless steel belted radial tires with non-directional on/off-road type tread mounted on disc wheel assemblies. Tire and wheel assemblies will be identical at all positions. Tires and wheels will be certified by the manufacturer for not less than 25 miles of continuous operation at 60 mph at the normal operational inflation pressure. A spare tire and wheel assembly will be provided; however, the spare tire and wheel assembly are not required to be mounted on the vehicle. Tires will be new. Retreads, recaps, or re-grooved tires will not be permitted.

Tire bead locks, where justified, may be installed on all tires and rims.

**JUSTIFICATION**

ADO/FAA Approval: → \_\_\_\_\_

3.3.10 Towing connections. The vehicle will be equipped with towing connections in accordance with NFPA 414. The vehicle will be designed for flat towing; the capability to lift and tow the vehicle is not required. The tow connections may intrude into the 30 degree approach angle.

3.3.11 Brake system. The vehicle will be equipped with a multi-channel all-wheel antilock brake system with at least one channel for each axle. The brakes will be automatic, self-adjusting and fully air-actuated. Brakes will be in accordance with CFR 49 CFR 393.40 through 393.42(b)), 393.43, and 393.43 through 393.52. The braking system, complete with all necessary components will include:

- a. Air compressor having a capacity of not less than 16 standard cubic feet per minute (SCFM).
- b. Air storage reservoir(s), each tank equipped with drain (bleed) valves, and with safety and check valves between the compressor and the reservoir tank.
- c. Automatic moisture ejector on each air storage reservoir. Manual air tank drains are acceptable if they are labeled, are centrally located in one compartment and are accessible by an individual standing at the side of the vehicle.
- d. Automatic slack adjusters on cam brakes or internal self-adjusting brakes on wedge brakes on all axles.
- e. Spring set parking brakes.

All components of the braking system will be installed in such a manner as to provide adequate road clearance when traveling over uneven or rough terrain, including objects liable to strike and cause damage to the brake system components. No part of the braking system will extend below the bottom of wheel rims, to ensure, in case of a flat tire, that the weight of the vehicle will be supported by the rim and the flat tire and not be imposed on any component of the braking system. Slack adjusters and air chambers will be located above the bottom edge of the axle carrier.

3.3.11.1 Air dryer. A replaceable cartridge desiccant air dryer will be installed in the air brake system. The dryer will have the capability of removing not less than 95 percent of the moisture in the air being dried. The dryer will have a filter to screen out oil and solid contaminants. The dryer will have an automatic self-cleaning cycle and a thermostatically controlled heater to prevent icing of the purge valve.

3.3.11.2 Compressed air shoreline or vehicle-mounted auxiliary air compressor. A flush mounted, check valved, auto-eject compressed air shoreline connection will be provided to maintain brake system pressure while the vehicle is not running. The shoreline will be flush mounted (not to extend outside the body line), located on the exterior of the vehicle, either on the left side rear corner of the cab, or at the rear of the vehicle. In lieu of a compressed air shoreline connection, the vehicle may be equipped with a 110 volt shoreline connected vehicle-mounted auxiliary air compressor. In lieu of a compressed air shoreline connection, the vehicle may be equipped with an electrical shoreline connected vehicle mounted auxiliary air compressor.

3.3.12 Steering. The vehicle will be equipped with power steering. Rear-wheel steering technology is not an approved vehicle option.

3.3.12.1 Steering effort. The steering system performance will be in accordance with NFPA 414.

3.3.12.2 Turning diameter. The fully loaded vehicle will have a wall to wall turning diameter of less than three times the overall length of the vehicle in both directions in accordance with NFPA 414.

3.3.13 License plate bracket. A lighted license plate bracket will be provided at the left rear and left front of the vehicle. The location of the left front bracket will be placed so as not to interfere with the operation of fire fighting systems.

3.4 Cab. The vehicle will have a fully enclosed two door cab of materials which are corrosion resistant, such as aluminum, stainless steel, or glass reinforced polyester construction. Steps and handrails will be provided for all crew doors, and at least one grab handle will be provided for each crew member, located inside the cab for use while the vehicle is in motion. The lowermost step(s) will be no more than 22 inches above level ground when the vehicle is fully loaded. A tilt and telescoping steering column will be provided.

3.4.1 Windshield and windows. The windshield and windows will be of tinted safety glass. Each door window will be capable of being opened far enough to facilitate emergency occupant escape in the event of a vehicle accident. The vehicle windows will have \_\_\_\_\_ control system.

3.4.2 Cab interior sound level. The maximum cab interior sound level will be in accordance with NFPA 414.

3.4.3 Instruments and controls. All instruments and controls will be illuminated and designed to prevent or produce windshield glare. Gauges will be provided for oil pressure, coolant temperature, and automatic transmission temperature. In addition to the instruments and controls required by NFPA 414, the following will be provided within convenient reach of the seated driver:

- a. Master warning light control switch,
- b. Work light switch(es), and
- c. Compartment "Door Open" warning light and intermittent alarm that sounds when a compartment door is open and the parking brakes are released or the transmission is in any position other than neutral.

3.4.4 Windshield deluge system. The vehicle will be equipped with a powered windshield deluge system. The deluge system will be supplied from the agent water tank and will have an independent pumping system. The deluge system activation switch will be located within reach of the seated driver and turret operator.

3.4.5 Forward Looking Infrared (FLIR). A forward looking infrared (FLIR) camera and in-cab monitor, meeting the requirements of NFPA 414, will be provided. In addition, the FLIR monitor described in NFPA 414 will have a minimum dimension of 10 in (25 cm) (measured diagonally) and be located in a position where it is visible to both the seated driver and turret operator.

3.4.6 Climate control system. The offeror/contractor's standard heater/defroster and air conditioning system will be provided. The climate control system will induct at least 60 cubic feet per minute of fresh air into the cab. Cab mounted components will be protected from inadvertent damage by personnel.

3.4.7 Seats. The driver seat will be adjustable fore and aft and for height. The turret operator's seat, located to the right front of the driver's seat, will be a fixed (non-suspension) type. Each seat will be provided with a Type 3 seat belt assembly (i.e., 3-point retractable restraint) in accordance with CFR 49 CFR 571.209. Seat belts must be of sufficient length to accommodate crew members in full Personal Protective Equipment (PPE).

3.4.7.1. Seat Options. Two types of seat options are allowed in the vehicle. A standard seat contains a hard/fixed back. For these seats, a remote-mounted bracket designed to store a Self-Contained Breathing Apparatus (SCBA) will be provided. The remote-mounted bracket for the driver and turret operator (at a minimum) must be placed inside the cab. The brackets for seat positions #3 and #4 may be placed outside of the cab if necessary. An SCBA seat, on the other hand, contains an opening which can accommodate someone wearing an SCBA. The chart below represents the user's stated preference for the vehicle seating configuration.

<b>Position</b>	<b>Standard</b>	<b>SCBA-Seat</b>	<b>N/A</b>
<b>Driver</b>			
<b>Turret</b>			
<b># 3</b>			
<b># 4</b>			

**JUSTIFICATION**

ADO/FAA Approval: → \_\_\_\_\_

3.4.8 Windshield wipers and washer. The vehicle will be equipped with electrically powered windshield wipers. The wiper arms and blades will be of sufficient length to clear the windshield area described by SAE J198, Windshield Wiper Systems - Trucks. Individual wiper controls will include a minimum of two speed settings and an intermittent setting. The wiper blades will automatically return to a park position, out of the line of vision. The vehicle will be equipped with a powered windshield washer system, including an electric fluid pump, a minimum one gallon fluid container, washer nozzles mounted to the wiper arms (wet arms), and a momentary switch.

3.4.9 Warning signs. Signs that state "Occupants must be seated and wearing a seat belt when apparatus is in motion" will be provided in locations that are visible from each seated position in accordance with NFPA 414."

3.4.10 Lateral accelerometer and/or stability control system. The vehicle will be equipped with a lateral accelerometer and/or an electronic stability control system in accordance with NFPA 414.

3.5 Body, compartments, and equipment mounting.

3.5.1 Body. The vehicle will have a corrosion-resistant body.

3.5.2 Compartments. The vehicle body will have lighted compartments in accordance with NFPA 414 with a minimum of 10 cubic feet of enclosed storage space.

3.5.2.1 Compartment doors. Storage compartments will have clear anodized aluminum, counterbalanced, non-locking, roll-up or single hinged doors as determined by the manufacturer. Door latch handles on roll-up doors will be full-width bar type. Door straps will be provided to assist in closing the compartment doors when the rolled up or hinged door height exceeds six feet above the ground.

3.5.2.2 Scuffplates. Replaceable scuffplates will be provided at each compartment threshold to prevent body damage from sliding equipment in and out of the compartments. The scuffplates will be securely attached to the compartment threshold but will be easily replaceable in the event of damage.

3.5.2.3 Drip rails. Drip rails will be provided over each compartment door.

3.5.2.4 Shelves. An adjustable and removable compartment shelf will be provided for every 18 inches of each vertical storage compartment door opening. Shelving adjustments will require no more than common hand tools, and will not require disassembly of fasteners. Shelves will support a minimum of 200 pounds without permanent deformation. Each shelf will be accessible to crew members standing on the ground or using a pull out and tip-down configuration. Each shelf will have drain holes located so as to allow for drainage of any water from the stowed equipment.

3.5.2.5 Drainage mats. Each compartment floor and shelf will be covered with a removable black mat designed to allow for drainage of any water from the stowed equipment.

3.5.3 SCBA storage tubes. A single compartment or tubes for storage of four SCBA bottles will be provided. If tubes are provided, two will be installed on each side of the vehicle. The tubes will be of sufficient size to accommodate the procuring agencies SCBA cylinders.

3.5.4 Ladder, handrails, and walkways. Ladder, stepping, standing, and walking surfaces will be in accordance with NFPA 414. Handrails will be provided in accordance with NFPA 414. The lowermost step(s) or ladder rungs will be no more than 22 inches (56 cm) above level ground when the vehicle is fully loaded. The lowermost steps may extend below the angle of approach or departure or ground clearance limits if they are designed to swing clear. The tread of the bottom steps must be at least 8 inches (20 cm) in width and succeeding steps at least 16 inches (40 cm) in width. The full width of all steps must have at least 6 inches (15 cm) of unobstructed toe room or depth when measured from, and perpendicular to, the front edge of the weight-bearing surface of the step.

3.5.5 Ancillary equipment. Ancillary equipment listed in NFPA 414 A.4.2.1 (1)-(17) is not covered by this Procurement Specification in accordance with AC 150/5220-10, Guide Specification for Aircraft Rescue and Fire Fighting (ARFF) Vehicles. Ancillary equipment is funded separately by other sources.

**NOTE:** Equipment funding will be obtained as a separate contract under the provisions of AC 150/5210-14, Aircraft Rescue and Fire Fighting Equipment, Tools, and Clothing.

3.6 Agent system.

3.6.1 Agent (fire) pump. The vehicle will be equipped with a centrifugal pump capable of providing the performance specified herein as prescribed by NFPA 414.

3.6.1.1 Agent system piping. All piping, couplings, and valves and associated components that come into contact with the agent will be in accordance with NFPA 414.

3.6.1.2 Tank to pump connection. A check valve and shutoff valve will be provided in each tank to pump line.

3.6.1.3 Piping, couplings, and valves. All agent system piping will conform to NFPA 414 criteria.

3.6.1.4 Overheat protection. The agent system will be equipped with an overheat protection system in accordance with NFPA 414. Overheat protection is not required on vehicles utilizing a pre-mixed pressurized foam system.

3.6.1.5 Pressure relief valves. The agent system will be equipped with pressure relief valves in accordance with NFPA 414.

3.6.1.6 Drains. The agent system will be equipped with a drainage system in accordance with NFPA 414.

3.6.2 Water tank. The vehicle will have a water tank with a manufacturer certified minimum capacity of at least 1500 gallons.

3.6.2.1 Water tank construction. The water tank will be constructed of passivated stainless steel, polypropylene, or Glass Reinforced Polyester (GRP) construction. All materials used will be capable of storing water, foam concentrate, and water/AFFF solutions.

3.6.2.2 Water tank overhead fill cover and drain. The water tank will be equipped with a 20 inch fill tower. The tower will be designed to allow for video inspection of the water tank interior. The water tank will incorporate a drainage system in accordance with NFPA 414.

3.6.2.3 Water tank overflow system and venting. The water tank will incorporate a venting system to relieve pressure on the tank during fill and discharge operations at maximum flow rates. It will have an overflow system to relieve excess fluid in the event of tank overflow. Drainage from the vent and overflow system will not flow over body panels or other vehicle components and will not be in the track of any of the tires. Tank vent hoses will be of the non-collapsible type.

3.6.2.4 Water tank top fill opening. A top fill opening of not less than 8 inches internal diameter with a readily removable ¼-inch mesh strainer will be provided. The fill opening may be incorporated as part of the manhole cover, and will be sized to accommodate a 2½-inch fill hose.

3.6.2.5 Water tank fill connections. The water tank will incorporate National Hose thread connections and will be in accordance with NFPA 414. If the vehicle is fitted with the "structural fire fighting capability option," the additional requirements listed in paragraph 3.6.8 must be incorporated.

3.6.3 Foam system. (**NOTE:** *The requirements of section 3.6.3 do not apply to pre-mixed pressurized foam systems.*)

3.6.3.1 Foam concentrate tank. The foam concentrate tank(s) will have a manufacturer certified working capacity sufficient for two tanks of water at the maximum tolerance specified in NFPA 412, Standard for Evaluating Aircraft Rescue and Fire-Fighting Foam Equipment for 3 to 6 percent foam concentrate (i.e., 7.0-percent).

3.6.3.1.1 Foam tank construction. The foam tank will be constructed of passivated stainless steel, polypropylene, or GRP construction. All materials used will be capable of storing foam concentrate.

3.6.3.1.2 Foam tank drain. The foam tank will incorporate a drain and drain valve. The valve will be on the left side of the vehicle and controlled by a crew member standing on the ground. The drain line will have a minimum 1½-inch I.D. The foam tank drain outlet will be located so that the contents of the tank can be drained into 5-gallon cans and 55-gallon drums.

3.6.3.1.3 Foam tank top fill trough. The foam tank will incorporate a top fill trough mounted in the top of the tank readily accessible to at least two crew members on top of the vehicle. The top fill trough will incorporate a cover, latch, and sealed so as to prevent spillage under any operating condition. The top fill trough will be designed to allow two standard 5-gallon foam concentrate containers to be emptied simultaneously. The top fill trough neck will extend sufficiently close to the bottom of the tank to reduce foaming to a minimum during the fill operation. The top fill trough will incorporate readily removable, rigidly constructed 10 mesh stainless steel, brass or polyethylene strainers. All components in and around the top fill trough will be constructed of materials that resist all forms of deterioration that could be caused by the foam concentrate or water.

3.6.3.2 Foam tank fill connections. The foam tank will incorporate a 1.5-inch National Hose thread female hose connection on [redacted] of the vehicle to permit filling by an external transfer hose at flow rates up to 25-gpm. The connections will be provided with chained-on long handled plugs or rocker lug plugs. The top of the connections will be no higher than 48 inches above the ground and readily accessible. The fill lines will incorporate check valves and readily removable, rigidly constructed ¼-inch mesh strainers. All components in the foam tank fill system will be constructed of materials that resist all forms of deterioration that could be caused by the foam concentrate or water.

3.6.3.2.1 Foam tank vent and overflow system. The foam tank will incorporate a vent system to relieve pressure on the tank during fill and discharge operations at maximum flow rates and an overflow system to relieve excess liquid in the event of tank overflow. Drainage from the vent and overflow system will not flow over body panels or other vehicle components and will not be in front of or behind any of the tires. Tank vent hoses will be of the non-collapsible type.

3.6.3.3 Foam transfer pump. A foam transfer pump will be provided and mounted in a compartment on the vehicle. The pump will be capable of transferring and drawing foam liquid concentrate at adjustable flow rates up to 25-gpm directly through the pump and loading


connections (see 3.6.3.2). All materials and components that come in contact with the foam will be compatible with the foam concentrate. The pump and its plumbing will have provisions for flushing with water from the water tank. A suitable length of hose with appropriate connections will be provided for filling the foam tank from an external foam storage container.

3.6.3.4 Foam flushing system. The foam concentrate system will be designed in accordance with NFPA 414 so that the system can be readily flushed with clear water.

3.6.3.5 Foam concentrate piping. All metallic surfaces of the piping and associated components that come into contact with the foam concentrate will be of brass, bronze, or passivated stainless steel. The foam concentrate piping will be in accordance with NFPA 414.

3.6.4 Foam proportioning system. The vehicle will have a foam proportioning system for Aqueous Film-Forming Foam (AFFF) (whether 3- or 6-percent foam concentrate) in accordance with NFPA 414. If a fixed orifice plate system is used, a plate will be provided for each percentage foam concentrate; the additional plate will be securely mounted in a protected location on the vehicle. A fire vehicle mechanic will be able to interchange the plates using common hand tools.


3.6.5 Primary vehicle turret. The vehicle will be equipped with a standard roof-mounted turret, high reach extendable turret, and/or high flow bumper mounted turret to serve as the primary source of agent delivery, as specified below:




3.6.6 Bumper turret. The vehicle will be equipped with a joystick controlled, constant flow, non-air-aspirating, variable stream type:


The bumper turret will be capable of discharging at a minimum flow rates of foam or water as specified by the user, with a pattern infinitely variable from straight stream to fully dispersed. The bumper turret will be capable of automatic oscillation, with the range of oscillation adjustable up to 90° each side of center (left and right) with vertical travel capabilities of +45°/-20° meeting section 4.20.2 in NFPA 414.

3.6.7 Preconnected handline(s). 200 foot, 1¾-inch pre-connected woven jacket handline(s), with a 1½-inch control valve and a pistol grip nozzle, will be located on (or accessible from) side of the vehicle. A safety system will be provided to prevent charging of the hose until the hose has been fully deployed. The handline(s) and nozzle(s) will be in accordance with NFPA 414, and will allow for a minimum of 95 gpm at 100 psi nozzle pressure. A control for charging handline will be provided for operation by both the driver and the turret operator.









3.9 Electrical systems and warning devices. The vehicle will have a 12-volt or 24-volt electrical and starting system in accordance with NFPA 414.

3.9.1 Alternator. An appropriate charging system, in accordance with NFPA 414, will be provided. The minimum continuous electrical load will include operation of the air conditioning system.

3.9.2 Batteries. Batteries will be of the maintenance-free type; addition of water will not be required during normal service life. The battery cover and vent system will be designed to prevent electrolyte loss during service and to keep the top of the battery free from electrolyte.

3.9.2.1 Battery compartment. The batteries will be enclosed in a weatherproof enclosure, cover, or compartment and be readily accessible.

3.9.3 Battery charger or conditioner. The vehicle will have a DC taper type battery charger or an automatic battery conditioner, or voltage monitoring system, providing a minimum 12 amp output. The charger/conditioner will be permanently mounted on the vehicle in a properly ventilated, accessible location. The charger/conditioner will be powered from the electrical shoreline receptacle (see 3.10.1). A charging indicator will be installed next to the receptacle. When a battery conditioner is provided, the conditioner will monitor the battery state of charge and, as necessary, automatically charge or maintain the batteries without gassing, depleting fluid level, overheating, or overcharging. A slave receptacle will be provided at the rear or on either side of the vehicle cab. Battery jump studs may be installed on the exterior of the battery box in lieu of a slave receptacle.

3.9.4 Electromagnetic interference. The vehicle electrical system will be in accordance with SAE J551-2 for electromagnetic interference.

3.9.5 Work lighting.

3.9.5.1 Cab interior lights. Cab interior light levels will be sufficient for reading maps or manuals. At least one red and one white cab interior dome light will be provided.

3.9.5.2 Compartment lights. White lighting sufficient to provide an average minimum illumination of 1.0 footcandle will be provided in each compartment greater than 4.0 cubic feet and having an opening greater than 144 square inches. Where a shelf is provided, this illumination will be provided both above and below the shelf. All compartments will be provided with weatherproof lights that are switched to automatically illuminate when compartment doors are opened and the vehicle master switch is in the 'on' position. Light switches will be of the magnetic (non-mechanical) type.

3.9.5.3 Ladder, step, walkway, and area lights. Non-glare white or amber lighting will be provided at ladders and access steps where personnel work or climb during night operations. In addition, ground lighting will be provided. Ground lights will be activated when the parking brake is set in accordance with AC 150/5220-10, Guide Specification for Aircraft Rescue and Fire Fighting (ARFF) Vehicles. These area lights will be controlled with three-way switches on the cab instrument panel and near the light sources. The switch located in the cab will be a

master switch and must be turned on before auxiliary switches near the light sources are operational.

3.9.5.4 Spot/Floodlights. Two spot/floodlights will be attached at the end of the primary turret or at the end of the HRET assembly. The lights will illuminate the area covered by the turret. Both lights will be controlled from switches in the cab. [REDACTED] lights will be used.

3.9.5.5 Flood Lights. Two [REDACTED] floodlights will be provided. One light will be mounted on the left and right sides of the vehicle. [REDACTED] lights will be used.

[REDACTED]

3.9.5.6 Scene Lights. A total of six high mounted floodlights will be provided to illuminate the work areas around the vehicle. Two lights will be mounted on the front and two will be mounted on each side of the vehicle. The lights will be powered by the vehicle alternator driven system or auxiliary generator, and the lights in the front will be controlled from switches in the cab. [REDACTED] lights will be used.

3.9.6 Audible warning devices.

3.9.6.1 Siren. The vehicle will be equipped with an electronic siren system. The amplifier unit will include volume control and selection of "Radio," "PA," "Manual," "Yelp," "Wail," and "Hi-Lo" (European) modes, and a magnetic noise canceling microphone. The amplifier, microphone, and controls will be within reach of the driver and the turret operator. Siren activating foot switches will be located in front of the driver and the turret operator. The siren speaker will be rated at 100 watts minimum and will be located in a guarded position as low and as far forward on the vehicle as practical.

3.9.6.2 Horn. Dual forward facing air horns will be installed in protected locations near the front of the vehicle. Air horn activating foot switches will be located in front of the driver and the turret operator.

3.9.7 Emergency warning lights. All emergency warning lights must meet the requirements of AC 150/5210-5. Where applicable, [REDACTED] lights will be used as the primary light type. Lighting units will be installed on the top front, sides, and rear of the vehicle to provide 360° visibility. A switch will be provided on the instrument panel to control all of the top, side, front and rear emergency warning lights. A switch will also be provided on the instrument panel to disable all lower emergency warning lights when desired. All lighting systems will meet NFPA 414 emergency lighting criteria.

3.9.7.1 Emergency warning light color. All emergency warning lights will meet the requirements of AC 150/5210-5.

3.9.7.2 Headlight flashing system. A high beam, alternating/flashing, headlight system will be provided. The headlight flasher will be separately switched from the warning light panel. All emergency warning lights will meet the requirements of AC 150/5210-5.

3.9.8 Radio circuit. The vehicle will have three separate 30 amp circuits with breakers and connections provided in a space adjacent to the driver and turret operator for installation of radios and other communications equipment after the vehicle has been delivered. To facilitate the installation of the communications equipment the manufacturer will provide three antennas pre-installed on top of the cab. ***Radios are an airport responsibility and not part of this specification.***

3.9.9 Power receptacles.

3.9.9.1 Primary power receptacles. The vehicle will have two duplex 15-amp 110-volt power receptacles, one installed adjacent to the cab door on each side of the vehicle. Each duplex receptacle will include one straight blade and one twist-lock connection. These outlets will be powered by the generator.


3.9.9.2 Auxiliary power receptacles. The vehicle will have 2-12-volt auxiliary power receptacles mounted adjacent to the driver and crew member positions, preferably in the instrument panel.



3.9.10 Auxiliary generator. A minimum   kilowatt (kW) (continuous rating), 120/240-volt, 60 hertz, diesel, hydraulic, or split shaft Power Takeoff (PTO)-driven generator will be provided.

3.10 Line voltage electrical system.

3.10.1 Electrical shoreline connection. The battery charger/conditioner will be powered from a covered, polarized, insulated, labeled, recessed (flush mounted), male, 110 volt AC auto-eject receptacle. The connection will be located on the exterior of the vehicle at the rear or on either side of the cab. A weatherproof charge meter will be installed next to the receptacle. A 15 amp rated, 110-120 volt, AC straight blade (non twist-lock) connector will be provided.



3.12 Quality of Workmanship. The vehicle, including all parts and accessories, will be fabricated in a thoroughly workmanlike manner. Particular attention will be given to freedom from blemishes, burrs, defects, and sharp edges; accuracy of dimensions, radii of fillets, and marking of parts and assemblies; thoroughness of welding, brazing, soldering, riveting, and painting; alignment of parts; tightness of fasteners; et cetera. The vehicle will be thoroughly cleaned of all foreign matter.

#### 4. REGULATORY REQUIREMENTS.

4.1 Recoverable Materials. The contractor is encouraged to use recovered materials to the maximum extent practicable, in accordance with Title 48: Federal Acquisition Regulations System, Part 2823—Environment, Conservation, Occupational Safety, and Drug-free Workplace, Subpart 2823.4 Use of Recovered Material, 403 Policy and 404 Procedures.

4.2 Green Procurement Program. Green Procurement Program (GPP) is a mandatory federal acquisition program that focuses on the purchase and use of environmentally preferable products and services. GPP requirements apply to all acquisitions using appropriated funds, including services and new requirements. FAR 23.404(b) applies and states the GPP requires 100% of EPA designated product purchase that are included in the Comprehensive Procurement Guidelines list that contains recovered materials, unless the item cannot be acquired:

- a. competitively within a reasonable timeframe;
- b. meet appropriate performance standards, or
- c. at a reasonable price.

The prime contractor is responsible for ensuring that all subcontractors comply with this requirement. Information on the GPP can be found at:

[http://www.dot.gov/ost/m60/DOT\\_policy\\_letters/apl8\\_04.pdf](http://www.dot.gov/ost/m60/DOT_policy_letters/apl8_04.pdf) or FAR 23.404(b):  
[http://www.acquisition.gov/far/current/html/Subpart%2023\\_4.html](http://www.acquisition.gov/far/current/html/Subpart%2023_4.html).

#### 5. PRODUCT CONFORMANCE PROVISIONS.

5.1 Classification of inspections. The inspection requirements specified herein are classified as follows:

- a. Performance inspection (see 5.2).
- b. Conformance inspection (see 5.3).

5.2 Performance inspection. The vehicle will be subjected to the examinations and tests described in 5.6.3.1 through 5.6.3.5 (if applicable). The contractor will provide or arrange for all test equipment, personnel, schedule, and facilities.

5.3 Conformance inspection. The vehicle will be subjected to the examinations and tests described in 5.6.3.1 through 5.6.3.5 (if applicable). The contractor will provide or arrange for all test equipment, personnel, and facilities.

5.4 Product conformance. The products provided will meet the performance characteristics of this PS, conform to the producer's own drawings, specifications, standards, and quality assurance practices, and be the same product offered for sale in the commercial marketplace. The purchaser reserves the right to require proof of such conformance.

5.5 Technical proposal. The offeror/contractor will provide an itemized technical proposal that describes how the proposed model complies with each characteristic of this PS; a paragraph by paragraph response to the characteristics section of this PS will be provided. The offeror/contractor will provide two copies of their commercial descriptive catalogs with their offer as supporting reference to the itemized technical proposal. The offeror/contractor will identify all modifications made to their commercial model in order to comply with the requirements herein. The vehicle furnished will comply with the "commercial item" definition of FAR 2.101 as of the date of award. The purchaser reserves the right to require the offeror/contractor to prove that their product complies with the referenced commerciality requirements and each conformance/performance characteristics of this PS.

5.6 Inspection requirements.

5.6.1 General inspection requirements. Apparatus used in conjunction with the inspections specified herein will be laboratory precision type, calibrated at proper intervals to ensure laboratory accuracy.

5.6.2 Test rejection criteria. Throughout all tests specified herein, the vehicle will be closely observed for the following conditions, which will be cause for rejection:

- a. Failure to conform to design or performance requirements specified herein or in the contractor's technical proposal.
- b. Any spillage or leakage of any liquid, including fuel, coolant, lubricant, or hydraulic fluid, under any condition, except as allowed herein.
- c. Structural failure of any component, including permanent deformation, or evidence of impending failure.
- d. Evidence of excessive wear.
- e. Interference between the vehicle components or between the vehicle, the ground, and all required obstacles, with the exception of normal contact by the tires.

- f. Misalignment of components.
- g. Evidence of undesirable roadability characteristics, including instability in handling during cornering, braking, and while traversing all required terrain.
- h. Conditions that present a safety hazard to personnel during operation, servicing, or maintenance.
- i. Overheating of the engine, transmission, or any other vehicle component.
- j. Evidence of corrosion.
- k. Failure of the fire fighting system and sub-systems.

### 5.6.3 Detailed inspection requirements.

5.6.3.1 Examination of product. All component manufacturers' certifications, as well as the prototype and production/operational vehicle testing outlined in Table 1, will be examined to verify compliance with the requirements herein. Attention will be given to materials, workmanship, dimensions, surface finishes, protective coatings and sealants and their application, welding, fastening, and markings. Proper operation of vehicle functions will be verified as defined by NFPA 414, Acceptance Criteria chapter. A copy of the vehicle manufacturer's certifications will be provided with each vehicle in accordance with NFPA 414. The airport may accept a manufacturer or third party certification for any/all prototype and production/operational vehicle testing performed prior to delivery which proves that the vehicle meets the performance parameters of NFPA 414.

**Table 1. Vehicle Test Data**

<b><i>NFPA 414 paragraph</i></b>	<b><i>Test</i></b>
<b>Production Vehicle Operational Tests (NFPA 414 - Section 6.4)</b>	
(6.4.1)	Vehicle Testing, Side Slope
(6.4.2)	Weight / Weight Distribution
(6.4.3)	Acceleration. <b>NOTE:</b> <i>With the modification that the instrumentation must be a GPS-based electronic data collection system.</i>
(6.4.4)	Top Speed
(6.4.5)	Brake Operational Test
(6.4.6)	Air System / Air Compressor Test
(6.4.7)	Agent Discharge Pumping Test
(6.4.8)	Dual Pumping System Test (As Applicable)
(6.4.9)	Pump and Maneuver Test
(6.4.10)	Hydrostatic Pressure Test
(6.4.11)	Foam Concentration Test
(6.4.12)	Primary Turret Flow Rate Test
(6.4.13)	Piercing/Penetration Nozzle Testing (As Applicable)
<b>Prototype Vehicle Tests (NFPA 414 – Section 6.3)</b>	
(6.3.1)	Rated Water and Foam Tank Capacity Test
(6.3.2)	Cornering Stability. <b>NOTE:</b> <i>With the modification that the evasive maneuver / double-lane change test must be conducted at 35 mph (56 kph).</i>

<b><i>NFPA 414 paragraph</i></b>	<b><i>Test</i></b>
(6.3.3)	Vehicle Dimensions
(6.3.4)	Driver Vision Measurement
(6.3.5)	Pump and Roll on a 40 Percent Grade
(6.3.6)	Electrical Charging System
(6.3.7)	Radio Suppression
(6.3.8)	Gradability Test
(6.3.9)	Body and Chassis Flexibility Test
(6.3.10)	Service/Emergency Brake Test
(6.3.11)	Service/Emergency Brake Grade Holding Test
(6.3.12)	Steering Control Test
(6.3.13)	Vehicle Clearance Circle Test
(6.3.14)	Agent Pump(s)/Tank Vent Discharge Test
(6.3.15)	Water Tank Fill and Overflow Test
(6.3.16)	Flushing System Test
(6.3.17)	Primary Turret Flow Rate Test
(6.3.18)	Primary Turret Pattern Test
(6.3.19)	Primary Turret Control Force Measurement
(6.3.20)	Primary Turret Articulation Test
(6.3.21)	Handline Nozzle Flow Rate Test
(6.3.22)	Handline Nozzle Pattern Test
(6.3.23)	Ground Sweep/Bumper Turret Flow Rate Test
(6.3.24)	Ground Sweep/Bumper Turret Pattern Control Test
(6.3.25)	Undertruck Nozzle Test
(6.3.26)	Foam Concentration/Foam Quality Test
(6.3.27)	Warning Siren Test
(6.3.28)	Propellant Gas
(6.3.29)	Pressure Regulation
(6.3.30)	AFFF Premix Piping and Valves
(6.3.31)	Pressurized Agent Purging and Venting
(6.3.32)	Complementary Agent Handline Flow Rate and Range
(6.3.33)	Dry Chemical Turret Flow Rate and Range
(6.3.34)	Cab Interior Noise Test

## 6. PACKAGING.

6.1 Preservation, packing, and marking will be as specified in the Procurement Specification, contract or delivery order.

6.2 The vehicle must be delivered with full operational quantities of lubricants, brake and hydraulic fluids, and cooling system fluid all of which must be suitable for use in the temperature range expected at the airport.

6.3 The vehicle must be delivered with one complete load of firefighting agents and propellants. One complete load is defined as all of the agents and propellants necessary for the

vehicle to be fully operational. One load would include, at a minimum: one fill of a foam tank; one fill of a dry chemical tank (if applicable); one fill of a halogenated tank (if applicable); one spare nitrogen cylinder for a dry chemical system (if applicable); and one spare argon cylinder for a halogenated system (if applicable). Agents and propellants for required testing or training are not included. For the initial training period, water should be used in place of other extinguishing agents. The manufacturer may pre-ship agents and propellants to a receiving airport to reduce overall procurement costs.

6.4. The vehicle manufacturer must provide initial adjustments to the vehicle for operational readiness and mount any ancillary appliances purchased through the vehicle manufacturer as part of the vehicle.

## 7. TRAINING.

7.1 Upon delivery of the vehicle to the airport, the manufacturer must, at no additional cost, provide the services of a qualified technician for five consecutive days (or up to 8 days for an high reach extendable turret) for training. This is considered sufficient time for the purchaser to adjust shift work schedules to get maximum employee attendance to training sessions at some point during the training period. During this time sufficient repetitive learning opportunities must be provided by the manufacturer to allow various shifts to complete the training requirements.

7.2 The technician must provide thorough instruction in the use, operation, maintenance and testing of the vehicle. This setup must include operator training for the primary operators, which will give them sufficient knowledge to train other personnel in the functional use of all fire fighting and vehicle operating systems. Prior to leaving the vehicle, the technician should review the maintenance instructions with the purchaser's personnel to acquaint them with maintenance procedures as well as how to obtain support service for the vehicle.

7.3 Training must include written operating instructions, electronic training aids (videos/power point), or other graphics that depict the step-by-step operation of the vehicle. Written instructions must include materials that can be used to train subsequent new operators.

## 8. REFERENCED DOCUMENTS.

### 8.1 Source of documents.

8.1.1 The CFR may be obtained from the Superintendent of Documents, U.S. Government Printing Office, Washington DC 20402.

Title 14, Code of Federal Regulations (CFR), Part 139, Certification of Airports (14 CFR Part 139)

Section 139.315 Aircraft Rescue and Firefighting: Index Determination.

Section 139.317 Aircraft Rescue and Firefighting: Equipment and Agents.

Section 139.319 Aircraft Rescue and Firefighting: Operational Requirements.

Title 49; Code of Federal Regulations (CFR), Part 393: Parts and Accessories Necessary for Safe Operation: Subpart C—Brakes.

Title 49; Code of Federal Regulations (CFR), Part 571, Motor Carrier Vehicle Safety Standards, Part 209, Standard No. 209; Seat Belt Assemblies

8.1.2 SAE documents may be obtained from SAE, Inc., 400 Commonwealth Drive, Warrendale PA 15096.

8.1.3 National Fire Protection Association (NFPA): NFPA documents may be obtained from NFPA, Batterymarch Park, Quincy MA 02269-9101.

NFPA 412, Standard for Evaluating Aircraft Rescue and Fire-Fighting Foam Equipment (2009 Edition)

NFPA 414, Standard for Aircraft Rescue and Fire Fighting Vehicles (2007 Edition)






NFPA 1901, Standard for Automotive Fire Apparatus (2009 Edition)

8.1.4 Federal Aviation Administration (FAA): FAA ACs may be obtained from the FAA website: [http://www.faa.gov/regulations\\_policies/advisory\\_circulars/](http://www.faa.gov/regulations_policies/advisory_circulars/)

AC 150/5220-10, Guide Specification for Aircraft Rescue and Fire Fighting (ARFF) Vehicles

AC 150/5210-5, Painting, Marking, and Lighting of Vehicles Used on an Airport

FAA Orders, Specifications, and Drawings may be obtained from: Federal Aviation Administration, ATO-W CM-NAS Documentation, Control Center, 800 Independence Avenue, SW, Washington, DC 20591. Telephone: (202) 548-5256, FAX: (202) 548-5501 and website: [http://www.faa.gov/about/office\\_org/headquarters\\_offices/ato/service\\_units/techops/atc\\_facilities/cm/cm\\_documentation/](http://www.faa.gov/about/office_org/headquarters_offices/ato/service_units/techops/atc_facilities/cm/cm_documentation/)



NOTES:

- DIMENSIONS OR NOTES CONTAINED WITHIN PARENTHESES ARE FOR REFERENCE ONLY.
- SEE ASME Y14.100 FOR DRAWING INTERPRETATION STANDARDS.

COMMERCIAL (EAR99)  
 THIS DRAWING IS SUBJECT TO THE EXPORT ADMINISTRATION REGULATIONS. YOU MAY NOT PROVIDE IT TO ANY PROHIBITED END-USERS OR FOR ANY PROHIBITED END-USES AS SET FORTH IN U.S. EXPORT CONTROLS.

THIS DRAWING IS PROVIDED ON A CONFIDENTIAL BASIS SUBJECT TO RETURN ON DEMAND BY OSHKOSH DEFENSE, LLC ("OSHKOSH"), WHICH RETAINS ANY AND ALL RIGHTS ASSOCIATED WITH IT AND THE ARTICLE OR ARTICLES IT REPRESENTS. DISCLOSURE, REPRODUCTION OR ALTERATION OF ANY PART OF THIS DRAWING, OR MANUFACTURE, USE OR SALE OF THE ARTICLE OR ARTICLES REPRESENTED, IS PROHIBITED WITHOUT THE PRIOR WRITTEN AUTHORIZATION OF OSHKOSH. ©OSHKOSH DEFENSE, LLC (unpublished).

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES LINEAR 3 PLACES ±0.020 TOLERANCES 2 PLACES ±0.06 ANGULAR 1 PLACE ±0.1 TOLERANCES 0 PLACES ±2° 3RD ANGLE PROJECTION	APPROVALS PREPARED U18606 2021/02/12 APPROVED MFG ENG CN CATIA V5R29	USER ID U18606	DATE 2021/02/12	OSHKOSH OSHKOSH DEFENSE, LLC OSHKOSH, WI 54903 USA
CONTRACT NO.	MIN: N/A FINISH: N/A	TITLE STRIKER 4X4 3.0		SIZE H 75Q65
REFERENCE:	MATERIAL:	SCALE 1:30		WEIGHT SHEET 01 OF 01

**EXHIBIT B  
INSURANCE REQUIREMENTS**

**A. INSURANCE**

The Vendor must provide a certificate of insurance and endorsement in accordance with the insurance requirements listed below.

The Vendor shall obtain and maintain, and require any subcontractors to obtain and maintain, at all times during its performance of the Agreement, insurance of the types and in the amounts set forth. For projects with a Completed Operations exposure, Vendor shall maintain coverage and provide evidence of insurance for two (2) years beyond final acceptance. All insurance policies shall be from responsible companies duly authorized to do business in the State of Florida and have an AM Best rating of A- VIII or better.

**B. INDEMNIFICATION:**

Vendor agrees to indemnify, pay the cost of defense, including attorney's fees, and hold harmless the County, its officers, employees and agents from all damages, suits, actions or claims, including reasonable attorney's fees incurred by the County, of any character brought on account of any injuries or damages received or sustained by any person, persons, or property, or in any way relating to or arising from the Agreement; or on account of any act or omission, neglect or misconduct of Contractor; or by, or on account of, any claim or amounts recovered under the Workers' Compensation Law; or of any other laws, regulations, ordinance, order or decree; or arising from or by reason of any actual or claimed trademark, patent or copyright infringement or litigation based thereon; or for any violation of requirements of the Americans with Disabilities Act of 1990, as may be amended, and all rules and regulations issued pursuant thereto (collectively the "ADA") except when such injury, damage, or violation was caused by the sole negligence of the County.

1. If Vendor does not currently meet insurance requirements, Vendor shall also include verification from their broker or agent that any required insurance requirements not met will be in place prior to the award of contract.

The Vendor shall email certificate that is compliant with the insurance requirements. If the certificate received is compliant, no further action may be necessary. The Certificate(s) of Insurance shall be signed by authorized representatives of the insurance companies shown on the Certificate(s). **The Certificate holder section shall indicate Pinellas County, a Subdivision of the State of Florida, 400 S Fort Harrison Ave, Clearwater, FL 33756. Pinellas County shall be named as an Additional Insured for General Liability. A Waiver of Subrogation for Workers Compensation shall be provided if Workers Compensation coverage is a requirement.**

2. Approval by the County of any Certificate(s) of Insurance does not constitute verification by the County that the insurance requirements have been satisfied or that the insurance policy shown on the Certificate(s) of Insurance is in compliance with the requirements of the Agreement. The County reserves the right to require a certified copy of the entire insurance policy, including endorsement(s), at any time during the contract period.
3. If any insurance provided pursuant to the Agreement expires or cancels prior to the completion of the work you will be notified by CTrax, the authorized Vendor of Pinellas County. Upon notification, renewal certificate(s) of Insurance and endorsement(s) should be furnished to Pinellas County Risk Management at [InsuranceCerts@pinellascounty.org](mailto:InsuranceCerts@pinellascounty.org) and to CTrax c/o JDi Data at [PinellasSupport@jdidata.com](mailto:PinellasSupport@jdidata.com) by the Vendor or their agent prior to the expiration

**EXHIBIT B  
INSURANCE REQUIREMENTS**

date.

- I. The Vendor shall also notify the County within twenty-four (72) hours after receipt, of any notices of expiration, cancellation, nonrenewal or adverse material change in coverage received by said Vendor from its insurer. Notice shall be given by email to Pinellas County Risk Management at [InsuranceCerts@pinellascounty.org](mailto:InsuranceCerts@pinellascounty.org). Nothing contained herein shall absolve Vendor of this requirement to provide notice.
  - II. Should the Vendor, at any time, not maintain the insurance coverages required herein, the County may terminate the Agreement.
4. If subcontracting is allowed under this Quote, the Primary Vendor shall obtain and maintain, at all times during its performance of the Agreement, insurance of the types and in the amounts set forth; and require any subcontractors to obtain and maintain, at all times during its performance of the Agreement, insurance limits as it may apply to the portion of the Work performed by the subcontractor; but in no event will the insurance limits be less than \$500,000 for Workers' Compensation/Employers' Liability, and \$1,000,000 for General Liability and Auto Liability if required below.

All subcontracts between the Vendor and its subcontractor shall be in writing and are subject to the County's prior written approval. Further, all subcontracts shall.

Require each subcontractor to be bound to the Vendor to the same extent the Vendor is bound to the County by the terms of the Contract Documents, as those terms may apply to the portion of the Work to be performed by the subcontractor;

- I. Provide for the assignment of the subcontracts from the Vendor to the County at the election of Owner upon termination of the Contract;
  - II. Provide that County will be an additional indemnified party of the subcontract;
  - III. Provide that the County will be an additional insured on all insurance policies required to be provided by the subcontractor except workers compensation and professional liability;
  - IV. Provide a waiver of subrogation in favor of the County and other Insurance terms and/or conditions as outlined below;
  - V. Assign all warranties directly to the County; and
  - VI. Identify the County as an intended third-party beneficiary of the subcontract. The Vendor shall make available to each proposed subcontractor, prior to the execution of the subcontract, copies of the Contract Documents to which the subcontractor will be bound by this Exhibit "B" and identify to the subcontractor any terms and conditions of the proposed subcontract which may be at variance with the Contract Documents.
5. Each insurance policy and/or certificate shall include the following terms and/or conditions:
- I. The Named Insured on the Certificate of Insurance and insurance policy must match the entity's name that responded to the solicitation and/or is signing the agreement with the County.

**EXHIBIT B  
INSURANCE REQUIREMENTS**

- II. Companies issuing the insurance policy, or policies, shall have no recourse against County for payment of premiums or assessments for any deductibles which all are at the sole responsibility and risk of Vendor.
- III. The term "County" or "Pinellas County" shall include all Authorities, Boards, Bureaus, Commissions, Divisions, Departments and Constitutional offices of County and individual members, employees thereof in their official capacities, and/or while acting on behalf of Pinellas County.
- IV. All policies shall be written on a primary, non-contributory basis.
- V. The minimum insurance requirements and limits for this Agreement, which shall remain in effect throughout its duration and for two (2) years beyond final acceptance for projects with a Completed Operations exposure, are as follows:

**C) Workers' Compensation Insurance:** Worker's Compensation Insurance is required if required pursuant to Florida law. If, pursuant to Florida law, Worker's Compensation Insurance is required, employer's liability, also known as Worker's Compensation Part B, is also required in the amounts set forth herein

Limits	Florida Statutory
Employers' Liability Limits	
Per Employee	\$500,000
Per Employee Disease	\$500,000
Policy Limit Disease	\$500,000

If Vendor is not required by Florida law, to carry Workers Compensation Insurance in order to perform the requirements of this Agreement, County Waiver Form for workers compensation must be executed, submitted, and accepted by Risk Management. Failure to obtain required Worker's Compensation Insurance without submitting and receiving a waiver from Risk Management constitutes a material breach of this Agreement.

**D) Commercial General Liability Insurance:** including, but not limited to, Independent Vendor, Contractual Liability Premises/Operations, Products/Completed Operations, and Personal Injury.

Limits	
Combined Single Limit Per Occurrence	\$1,000,000
Products/Completed Operations Aggregate	\$ 2,000,000
Personal Injury and Advertising Injury	\$ 1,000,000
General Aggregate	\$ 2,000,000

**E) Business Automobile or Trucker's/Garage Liability Insurance** covering owned, hired, and non-owned vehicles. If the Proposer does not own any vehicles, then evidence of Hired and Non-owned coverage is sufficient. Coverage shall be on an "occurrence" basis, such insurance to include coverage for loading and unloading hazards, unless Proposer can show that this coverage exists under the Commercial General Liability policy.

Limit

**EXHIBIT B  
INSURANCE REQUIREMENTS**

Combined Single Limit Per Accident	\$1,000,000
------------------------------------	-------------

**F) Property Insurance:** Vendor will be responsible for all damage to its own property, equipment and/or materials.

## EXHIBIT C

**PAYMENT SCHEDULE  
SERVICES AGREEMENT**

Total lump sum cost for Airport Rescue Fire Fighting Truck as indicated in the scope of work, inclusive of vehicle, warranty, ancillary equipment, and any associated delivery costs.	<b>Total Lump Sum Cost</b>
	<b>\$783,255.00</b>

The items listed below were competitively quoted as separate line items. Each of the below items is included in the above total lump sum cost .

ITEM NO.	ANCILLARY EQUIPMENT	COST
1	Axe, rescue, large, non-wedge type with 36 in fiberglass handle; to include scabbard and pick head cover and mounting equipment	\$244.00
2	Driver's Enhanced Vision System (DEVS) AC 150/5210-19A	\$40,164.00
3	Axe, flat head, fiberglass handle - 36 in with mounting bracket, (for married set w/Halligan Tool)	\$183.00
4	2- Portable rechargeable, weatherproof, intrinsically safe hand-held lanterns having a minimum 25,000 beam candle power rating with straps. Chargers to be mounted in cab wired into vehicle electrical system for charging.	\$635.00
5	2- Mounting brackets with installation for 20lb B/C UL Fire extinguishers	\$87.00
6	1- Mounting bracket with installation for a 30lb Class D Fire extinguisher	\$52.00
7	Vehicle shall have the capability of performing an Input based style foam test	\$1,025.00
8	Tire Pressure Monitoring system (TPMS)	\$1,112.00
9	Seatbelt Monitor System	\$1,729.00
10	120v shoreline Aux air compressor	\$1,543.00
11	360 Birdseye View camera system	\$1,687.00
12	3 - Under Truck Nozzles	\$1,421.00
13	Upgrade roof and bumper turrets to Akrochem Master stream	\$2,780.00
14	Pike Pole mounting brackets	\$503.00
15	Whelen Emergency Light and Siren package	\$0.00
16	eDRAULIC cutter/spreader with 2 spare batteries, 1 extra charging	\$15,499.00
17	eDraulic Combi Tool	\$1.00
18	Extended Warranties	\$4,100.00

**SERVICES AGREEMENT**

**EXHIBIT D**

**PAYMENT/INVOICES**

**PAYMENT/INVOICES:**

SUPPLIER shall submit invoices for payment due as provided herein with such documentation as required by Pinellas County and all payments shall be made in accordance with the requirements of Section 218.70 *et. seq.*, Florida Statutes, "The Local Government Prompt Payment Act." Invoices shall be submitted to the address below unless instructed otherwise on the purchase order, or if no purchase order, by the ordering department:

Finance Division Accounts Payable  
Pinellas County Board of County Commissioners  
P. O. Box 2438  
Clearwater, FL 33757

Each invoice shall include, at a minimum, the Supplier's name, contact information and the standard purchase order number. In order to expedite payment, it is recommended the Supplier also include the information shown in below. The County may dispute any payments invoiced by SUPPLIER in accordance with the County's Dispute Resolution Process for Invoiced Payments, established in accordance with Section 218.76, Florida Statutes, and any such disputes shall be resolved in accordance with the County's Dispute Resolution Process.

**INVOICE INFORMATION:**

**Supplier Information** Company name, mailing address, phone number, contact name and email address as provided on the PO

<b>Remit To</b>	Billing address to which you are requesting payment be sent
<b>Invoice Date</b>	Creation date of the invoice
<b>Invoice Number</b>	Company tracking number
<b>Shipping Address</b>	Address where goods and/or services were delivered
<b>Ordering Department</b>	Name of ordering department, including name and phone number of contact person
<b>PO Number</b>	Standard purchase order number
<b>Ship Date</b>	Date the goods/services were sent/provided
<b>Quantity</b>	Quantity of goods or services billed
<b>Description</b>	Description of services or goods delivered
<b>Unit Price</b>	Unit price for the quantity of goods/services delivered
<b>Line Total</b>	Amount due by line item
<b>Invoice Total</b>	Sum of all of the line totals for the invoice

Pinellas County offers a credit card payment process (ePayables) through Bank of America. Pinellas County does not charge vendors to participate in the program; however, there may be a charge by the company that processes your credit card transactions. For more information please visit Pinellas County purchasing website at [www.pinellascounty.org/purchase](http://www.pinellascounty.org/purchase).

## SERVICES AGREEMENT

### EXHIBIT E

#### DISPUTE RESOLUTION FOR PINELLAS COUNTY BOARD OF COUNTY COMMISSIONERS IN MATTERS OF INVOICE PAYMENTS:

Payment of invoices for work performed for Pinellas County Board of County Commissioners (County) is made, by standard, in arrears in accordance with Section 218.70, et. seq., Florida Statutes, the Local Government Prompt Payment Act.

If a dispute should arise as a result of non-payment of a payment request or invoice the following Dispute Resolution process shall apply:

- A. Pinellas County shall notify a vendor in writing within ten (10) days after receipt of an improper invoice, that the invoice is improper. The notice should indicate what steps the vendor should undertake to correct the invoice and resubmit a proper invoice to the County. The steps taken by the vendor shall be that of initially contacting the requesting department to validate their invoice and receive a sign off from that entity that would indicate that the invoice in question is in keeping with the terms and conditions of the agreement. Once sign off is obtained, the vendor should then resubmit the invoice as a "Corrected Invoice" to the requesting department which will initiate the payment timeline.
  - 1.) Requesting department for this purpose is defined as the County department for whom the work is performed.
  - 2.) Proper invoice for this purpose is defined as an invoice submitted for work performed that meets prior agreed upon terms or conditions to the satisfaction of Pinellas County.
- B. Should a dispute result between the vendor and the County about payment of a payment request or an invoice then the vendor should submit their dissatisfaction in writing to the Requesting Department. Each Requesting Department shall assign a representative who shall act as a "Dispute Manager" to resolve the issue at departmental level.
- C. The Dispute Manager shall first initiate procedures to investigate the dispute and document the steps taken to resolve the issue in accordance with section 218.76 Florida Statutes. Such procedures shall be commenced no later than forty-five (45) days after the date on which the payment request or invoice was received by Pinellas County, and shall not extend beyond sixty (60) days after the date on which the payment request or invoice was received by Pinellas County.
- D. The Dispute Manager should investigate and ascertain that the work, for which the payment request or invoice has been submitted, was performed to Pinellas County's satisfaction and duly accepted by the Proper Authority. Proper Authority for this purpose is defined as the Pinellas County representative who is designated as the approving authority for the work performed in the contractual document. The Dispute Manager shall perform the required investigation and arrive at a solution before or at the sixty (60) days timeframe for resolution of the dispute, per section 218.76, Florida Statutes. The County Administrator or his or her designee shall be the final arbiter in resolving the issue before it becomes a legal matter. The County Administrator or his or her designee will issue their decision in writing.
- E. Pinellas County Dispute Resolution Procedures shall not be subject to Chapter 120 of the Florida Statutes. The procedures shall also, per section 218.76, Florida Statutes, not be intended as an administrative proceeding which would prohibit a court from ruling again on any action resulting from the dispute.

**SERVICES AGREEMENT**

**EXHIBIT E**

**DISPUTE RESOLUTION FOR PINELLAS COUNTY BOARD OF COUNTY COMMISSIONERS IN MATTERS OF INVOICE PAYMENTS:**

- F. Should the dispute be resolved in the County's favor interest charges begin to accrue fifteen (15) days after the final decision made by the County. Should the dispute be resolved in the vendor's favor the County shall pay interest as of the original date the payment was due.
  
- G. For any legal action to recover any fees due because of the application of sections 218.70 et. seq., Florida Statutes, an award shall be made to cover court costs and reasonable attorney fees, including those fees incurred as a result of an appeal, to the prevailing party. If it is found that the non-prevailing party held back any payment that was the reason for the dispute without having any reasonable lawful basis or fact to dispute the prevailing party's claim to those amounts.

EXHIBIT D

PAYMENT/INVOICES

**PAYMENT/INVOICES:**

SUPPLIER shall submit invoices for payment due as provided herein with such documentation as required by Pinellas County and all payments shall be made in accordance with the requirements of Section 218.70 *et. seq.*, Florida Statutes, "The Local Government Prompt Payment Act." Invoices shall be submitted to the address below unless instructed otherwise on the purchase order, or if no purchase order, by the ordering department:

Finance Division Accounts Payable  
Pinellas County Board of County Commissioners  
P. O. Box 2438  
Clearwater, FL 33757

Each invoice shall include, at a minimum, the Supplier's name, contact information and the standard purchase order number. In order to expedite payment, it is recommended the Supplier also include the information shown in below. The County may dispute any payments invoiced by SUPPLIER in accordance with the County's Dispute Resolution Process for Invoiced Payments, established in accordance with Section 218.76, Florida Statutes, and any such disputes shall be resolved in accordance with the County's Dispute Resolution Process.

**INVOICE INFORMATION:**

**Supplier Information** Company name, mailing address, phone number, contact name and email address as provided on the PO

- Remit To** Billing address to which you are requesting payment be sent
- Invoice Date** Creation date of the invoice
- Invoice Number** Company tracking number
- Shipping Address** Address where goods and/or services were delivered
- Ordering Department** Name of ordering department, including name and phone number of contact person
- PO Number** Standard purchase order number
- Ship Date** Date the goods/services were sent/provided
- Quantity** Quantity of goods or services billed
- Description** Description of services or goods delivered
- Unit Price** Unit price for the quantity of goods/services delivered
- Line Total** Amount due by line item
- Invoice Total** Sum of all of the line totals for the invoice

Pinellas County offers a credit card payment process (ePayables) through Bank of America. Pinellas County does not charge vendors to participate in the program; however, there may be a charge by the company that processes your credit card transactions. For more information please visit Pinellas County purchasing website at [www.pinellascounty.org/purchase](http://www.pinellascounty.org/purchase).

## EXHIBIT E

**DISPUTE RESOLUTION FOR PINELLAS COUNTY BOARD OF COUNTY COMMISSIONERS IN MATTERS OF INVOICE PAYMENTS:**

Payment of invoices for work performed for Pinellas County Board of County Commissioners (County) is made, by standard, in arrears in accordance with Section 218.70, et. seq., Florida Statutes, the Local Government Prompt Payment Act.

If a dispute should arise as a result of non-payment of a payment request or invoice the following Dispute Resolution process shall apply:

- A. Pinellas County shall notify a vendor in writing within ten (10) days after receipt of an improper invoice, that the invoice is improper. The notice should indicate what steps the vendor should undertake to correct the invoice and resubmit a proper invoice to the County. The steps taken by the vendor shall be that of initially contacting the requesting department to validate their invoice and receive a sign off from that entity that would indicate that the invoice in question is in keeping with the terms and conditions of the agreement. Once sign off is obtained, the vendor should then resubmit the invoice as a "Corrected Invoice" to the requesting department which will initiate the payment timeline.
  - 1.) Requesting department for this purpose is defined as the County department for whom the work is performed.
  - 2.) Proper invoice for this purpose is defined as an invoice submitted for work performed that meets prior agreed upon terms or conditions to the satisfaction of Pinellas County.
- B. Should a dispute result between the vendor and the County about payment of a payment request or an invoice then the vendor should submit their dissatisfaction in writing to the Requesting Department. Each Requesting Department shall assign a representative who shall act as a "Dispute Manager" to resolve the issue at departmental level.
- C. The Dispute Manager shall first initiate procedures to investigate the dispute and document the steps taken to resolve the issue in accordance with section 218.76 Florida Statutes. Such procedures shall be commenced no later than forty-five (45) days after the date on which the payment request or invoice was received by Pinellas County, and shall not extend beyond sixty (60) days after the date on which the payment request or invoice was received by Pinellas County.
- D. The Dispute Manager should investigate and ascertain that the work, for which the payment request or invoice has been submitted, was performed to Pinellas County's satisfaction and duly accepted by the Proper Authority. Proper Authority for this purpose is defined as the Pinellas County representative who is designated as the approving authority for the work performed in the contractual document. The Dispute Manager shall perform the required investigation and arrive at a solution before or at the sixty (60) days timeframe for resolution of the dispute, per section 218.76, Florida Statutes. The County Administrator or his or her designee shall be the final arbiter in resolving the issue before it becomes a legal matter. The County Administrator or his or her designee will issue their decision in writing.
- E. Pinellas County Dispute Resolution Procedures shall not be subject to Chapter 120 of the Florida Statutes. The procedures shall also, per section 218.76, Florida Statutes, not be intended as an administrative proceeding which would prohibit a court from ruling again on any action resulting from the dispute.

EXHIBIT E

**DISPUTE RESOLUTION FOR PINELLAS COUNTY BOARD OF COUNTY COMMISSIONERS IN MATTERS OF INVOICE PAYMENTS:**

- F. Should the dispute be resolved in the County's favor interest charges begin to accrue fifteen (15) days after the final decision made by the County. Should the dispute be resolved in the vendor's favor the County shall pay interest as of the original date the payment was due.
  
- G. For any legal action to recover any fees due because of the application of sections 218.70 et. seq., Florida Statutes, an award shall be made to cover court costs and reasonable attorney fees, including those fees incurred as a result of an appeal, to the prevailing party. If it is found that the non-prevailing party held back any payment that was the reason for the dispute without having any reasonable lawful basis or fact to dispute the prevailing party's claim to those amounts.